STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6 - SUNDERLAND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 1.785, RT	G/H	D3-1	36	6		Sunderland Hill Rd						X													REMOVE SIGN			
		A/B	D3-1	54	12		Bacon Hollow Rd	4.50					X		X	2		X								INSTALL NEW SIGN ON 2-POSTS AT SAME LOCATION AS REMOVED SIGN ASSEMBLY		12	
NB	MM 1.785, RT	D	R1-1	30	30		STOP	5.00					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
NB	MM 1.810, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 290 FT NORTH OF AND ACROSS FROM POLE# 114/78	X		
SB	MM 1.910, RT		D3-1	36	12		Dunlap Rd	3.00					X													INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		12	
		H	R2-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
SB	MM 1.920, LT	G	W14-2	30	30		NO OUTLET NOT IN FIELD	6.25					~~X~~		X	1		X								INSTALL NEW SIGN AND POST 50 FT WEST OF SUNDERLAND ROAD ON THE NORTH SIDE OF DUNLAP ROAD	X		
SB	MM 2.193, LT	E/F	D3-1	54	12		Maggies Run Rd	4.50					X		X X	2		X								INSTALL NEW SIGN AND POST AT SAME LOCATION		12	
SB	MM 2.194, LT	H	R2-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
SB	MM 2.205, LT	G	W14-2	30	30		NO OUTLET	6.25								1		X								INSTALL NEW SIGN AND POST 50 FT WEST OF SUNDERLAND ROAD ON THE NORTH SIDE OF MAGGIES RUN ROAD	X		
SB	MM 2.232, LT	F	R2-1	30	30		SPEED LIMIT 35	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 428 FT SOUTH OF POLE# 128/92	X		
NB	MM 2.298, RT	A	W7-1	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 79 SOUTH OF AND ACROSS FROM POLE# 128/92	X		
NB	MM 2.241, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 512 NORTH OF AND ACROSS FROM POLE# 128/92	X		
NB	MM 2.541, RT	A	W1-3 R	30	30								X		X											REMOVE SIGN AND POST			
		A	W7-1	30	30								X													REMOVE SIGN			
							SHEET SUBTOTALS	SF 63.25	SF	EA 13			EA 13	EA 11	EA 13		FT 195			EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER:
DESIGNED BY: N. AVERY
SUNDERLAND TRAFFIC SIGN SUMMARY 6

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 67 OF 78