STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8 - SUNDERLAND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 2.909, LT	E	WI-8 R	18	24		B-B	3.00								~~2~~ 1		X								INSTALLED BACK-TO-BACK ON A ~~SIGN BRACKET AND A SINGLE POST~~ 766 FT NORTH OF AND ACROSS FROM POLE# 104	X		
		F	WI-8 L	18	24			3.00										X									X		
SB	MM 2.932, LT	E	WI-8 R	18	24		B-B	3.00								~~2~~ 1		X								INSTALLED BACK-TO-BACK ON A ~~SIGN BRACKET AND A SINGLE POST~~ 887 FT NORTH OF AND ACROSS FROM POLE# 104	X		
		F	WI-8 L	18	24			3.00										X									X		
SB	MM 2.959, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 137 FT SOUTH OF POLE# 105	X		
SB	MM 2.997, LT	F	TOWN SIGN	30	30		COVERED BRIDGE						X		X											REMOVE SIGN AND POST			
		F	WI2-2	36	36		8'-2"	9.00					X			2		X								INSTALL NEW SIGNS ON 2-POSTS 63 FT NORTH OF POLE# 105	X		
		F	WI6-3P	30	12		3 MILES	2.50																		INSTALL BENEATH BRIDGE CLEARANCE SYMBOL SIGN AT THE CORRECT SIGN HEIGHT	X		
SB	MM 3.006, LT	E/F	D3-1	36	12		~~Dunham Rd~~ NOT IN FIELD	3.00					~~X~~													INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		12	
		H	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
SB	MM 3.014, LT	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00					X		X	1		X								INSTALL NEW SIGN AND POST ON LEFT SIDE OF TOWN HIGHWAY AS PER STANDARD	X		
		G	R2-1	30	30		SPEED LIMIT 25	5.00					X													INSTALL BENEATH BRIDGE LEGAL LOAD LIMIT SIGN AT THE CORRECT SIGN HEIGHT	X		
NB	MM 3.014, RT	A	M4-5	24	12		TO	2.00								1		X								INSTALL NEW SIGN AND POST 100 FT SOUTH OFTHE CENTER OF HILL FARM ROAD INTERSECTION WITH SUNDERLAND ROAD			E-136b
		A	M1-5	24	24		VERMONT 7A	4.00																		INSTALL BENEATH "TO" AUXILIARY MARKER SIGN AT THE CORRECT SIGN HEIGHT			E-136b
		A	M6-1L	21	15			2.19																		INSTALL BENEATH STATE ROUTE MARKER SIGN AT THE CORRECT SIGN HEIGHT			E-136b
SB	MM 3.015, LT	E/F	D3-1	24	6		Dunham Rd						X		X											REMOVE SIGN AND POST			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

			EA	EA	EA	EA	EA	EA		FT	FT	FT		LB	LB	LB	LB
						8		5			120						
SHEET SUBTOTALS	SF 55.94	SF	EA 8				EA 5		EA 8	FT 120			EA	LB			

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER:
DESIGNED BY: N. AVERY
SUNDERLAND TRAFFIC SIGN SUMMARY 8

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 69 OF 78