STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 10 - SUNDERLAND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	FOUNDATION	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
NB	MM 3.908, RT	C	R2-1	24	30		SPEED LIMIT 25	5.00					X		X	1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION ON SOUTH (LEFT) SIDE OF BOROUGH ROAD	X		
SB	MM 3.910, LT	G	R1-1	24	30		STOP						X		X											REMOVE SIGN AND POST			
NB	MM 3.916, RT	C/D	D3-1	30	6		Sunderland Hill Rd						X		X											REMOVE SIGN AND POST			
NB	MM 3.768, RT	A/B	D3-1	36	12		Borough Rd	3.00					X													INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		12	
		D	R1-1	30	30		~~STOP~~ NOT IN FIELD	6.25					~~X~~		X	1		X								INSTALL NEW SIGN AND POST ON RIGHT SIDE OF TOWN HIGHWAY AS PER STANDARD	X		
SB	MM 3.923, LT	F	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE SIGN AND POST	X		
NB	MM 3.941, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST 11FT SOUTH OF AND ACROSS FROM POLE# 32/35/1	X		
NB	MM 4.189, RT	A	W1-4L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 42 FT NORTH OF AND ACROSS FROM POLE# 8	X		
NB	MM 4.243, RT	E F	W1-8 R W1-8 L	18 18	24 24		B-B	3.00 3.00					X		X	1		X								INSTALLED BACK-TO-BACK ON A ~~SIGN BRACKET AND A SINGLE POST~~ 327 FT NORTH OF AND ACROSS FROM POLE# 8	X X		
NB	MM 4.255, RT	A	W1-8 L	18	24								X		X											REMOVE SIGN AND POST			
NB	MM 4.270, RT	A B	W1-8 R W1-8 L	18 18	24 24		B-B	3.00 3.00					X		X	1		X								INSTALLED BACK-TO-BACK ON A ~~SIGN BRACKET AND A SINGLE POST~~ 470 FT SOUTH OF AND ACROSS FROM POLE# 81	X X		
NB	MM 4.281, RT	A	W1-8 L	18	24								X		X											REMOVE SIGN AND POST			
NB	MM 4.293, RT	A B	W1-8 R W1-8 L	18 18	24 24		B-B	3.00 3.00								1		X								INSTALLED BACK-TO-BACK ON A ~~SIGN BRACKET AND A SINGLE POST~~ 591FT SOUTH OF AND ACROSS FROM POLE# 101	X X		
SB	MM 4.398, LT	F	W1-6 L	24	30			8.00								2		X								INSTALL NEW SIGN ON 2-POSTS 180' SOUTH OF POLE# 25T/50 AT RIGHT ANGLES TO APPROACHING TRAFFIC DO NOT BLOCK RR CONTROL BOX	X		
SB	MM 4.422, LT	E	W1-6 R	24	30			8.00								2		X								INSTALL NEW SIGN ON 2-POSTS 21FT SOUTH OF POLE# 25T/50 AT RIGHTANGLES TO APPROACHING TRAFFIC	X		
										EA	EA	EA	EA 10	EA	EA 9		FT	FT 165	FT		LB	LB	LB	LB					
							SUNDERLAND SHEET TOTALS	SF 59.50	SF	EA 10				EA 9		EA 11	FT 165			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER:
DESIGNED BY: N. AVERY
SUNDERLAND TRAFFIC SIGN SUMMARY 10

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 71 OF 78