STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 03

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (In)	SIGN DIMENSIONS HEIGHT (In)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (In) lb/ft 1.75	SQUARE STEEL (In) lb/ft 2.0	SQUARE STEEL (In) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0	TUBULAR ALUMINUM Ø (In) lb/ft 4.0	TUBULAR ALUMINUM Ø (In) lb/ft 4.0 MOD	FOUND-ATION	TUBULAR STEEL Ø (In) lb/ft 3.0	TUBULAR STEEL Ø (In) lb/ft 3.5	TUBULAR STEEL Ø (In) lb/ft 4.0	TUBULAR STEEL Ø (In) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
BURLINGTON LS-2 (CONT.)																																				
29		1 1	24 24	30 30	5.00 5.00						1						X	X																R2-1 S5-2	- -	SHSM SHSM
31		1 1	24 30	48 42	- -																												S5-1 NEW SOLAR-POWERED RSFS ASSEMBLY WITH NEW FLASHING BEACONS	- -	SHSM -
34							1 1				1					X		X																MOUNT SALVAGED SIGNS ON NEW POST	- -	- -
36		1 1	36 24	36 8	9.00 1.33						2					X		X																S1-1 (FLUORESCENT YELLOW-GREEN) S4-3P (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
											FT	FT	FT	FT	FT 45	FT 15		EA	LB	LB	LB		LB	LB	LB	LB								
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VAOT "SIGN POST DESIGN GUIDELINE."		TOTALS	SF 20.33	SF	EA. 2	SF						FT			FT 60					LB			EA.	LB				EA.	EA.	LB					

PROJECT NAME: STATEWIDE SRTS PROJECTS
PROJECT NUMBER: STP SRIN(25)

FILE NAME: ...\06 Champlain LS-2 TSS.dgn
PROJECT LEADER: G. GOYETTE
DESIGNED BY: STANTEC
BURLINGTON TSS-3

PLOT DATE: 12/28/2012
DRAWN BY: G. BURGMEIER
CHECKED BY: G. GOYETTE
SHEET 23 OF 35

Stantec