STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 06

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (In)	SIGN DIMENSIONS HEIGHT (In)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (In) lb/ft 1.75	SQUARE STEEL (In) lb/ft 2.0	SQUARE STEEL (In) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0	TUBULAR ALUMINUM Ø (In) lb/ft 4.0	TUBULAR ALUMINUM Ø (In) lb/ft 4.0 MOD	FOUND-ATION	TUBULAR STEEL Ø (In) lb/ft 3.0	TUBULAR STEEL Ø (In) lb/ft 3.5	TUBULAR STEEL Ø (In) lb/ft 4.0	TUBULAR STEEL Ø (In) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
POULTNEY WEST LS-5																																			
1	SCHOOL	1	36	36	9.00						2					X		X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	8	1.33																												S4-3P (FLUORESCENT YELLOW-GREEN)	-	SHSM
3	STOP	1	30	30	6.25						1					X		X															R1-1	-	SHSM
5		1	36	36	9.00						2					X		X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												W16-7pR (RIGHT) (FLUORESCENT YELLOW-GREEN)	-	SHSM
7	YORK ST STOP						1																										MOUNT ABOVE STOP SIGN ON EXISTING BRACKET		
		1	30	30	6.25				1																								R1-1 MOUNT ON EXISTING BRACKET	-	SHSM
8	SPEED LIMIT 25	1	24	30	-																												R2-1	-	SHSM
	YOUR SPEED 29	1	30	42	-																												NEW SOLAR-POWERED RSFS ASSEMBLY WITH POST AND BREAKAWAY FOUNDATION	-	-
10	SCHOOL	1	36	36	9.00						2					X		X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	8	1.33																												S4-3P (FLUORESCENT YELLOW-GREEN)	-	SHSM
11	STOP	1	30	30	6.25				1																								R1-1	-	SHSM
13		1	36	36	9.00						2					X		X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												W16-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
15	SCHOOL	1	36	36	9.00						2					X		X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	8	1.33																												S4-3P (FLUORESCENT YELLOW-GREEN)	-	SHSM
17		1	36	36	9.00						2					X		X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												W16-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
19	STOP	1	30	30	6.25						1					X		X															R1-1	-	SHSM
20	SPEED LIMIT 25	1	24	30	-																												R2-1	-	SHSM
	YOUR SPEED 29	1	30	42	-																												NEW SOLAR-POWERED RSFS ASSEMBLY WITH POST AND BREAKAWAY FOUNDATION	-	-
22	STOP	1	30	30	6.25						1					X		X															R1-1	-	SHSM
23	NO PARKING ANY TIME	1	12	18	-		1																										R7-1	-	SHSM
												FT	FT	FT	FT	FT 225	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 95.24	SF	EA. 2	SF				FT			FT 225					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VAOT "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: STATEWIDE SRTS PROJECTS
PROJECT NUMBER: STP SRIN(25)

FILE NAME: ...\09 Poultney West LS-5 TSS.dgn PLOT DATE: 12/28/2012
PROJECT LEADER: G. GOYETTE DRAWN BY: G. BURGMEIER
DESIGNED BY: STANTEC CHECKED BY: G. GOYETTE
POULTNEY WEST TSS-6 SHEET 26 OF 35