STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 07

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (In)	SIGN DIMENSIONS HEIGHT (In)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (In) lb/ft 1.75	SQUARE STEEL (In) lb/ft 2.0	SQUARE STEEL (In) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0	TUBULAR ALUMINUM Ø (In) lb/ft 4.0	TUBULAR ALUMINUM Ø (In) lb/ft 4.0 MOD	FOUND-ATION	TUBULAR STEEL Ø (In) lb/ft 3.0	TUBULAR STEEL Ø (In) lb/ft 3.5	TUBULAR STEEL Ø (In) lb/ft 4.0	TUBULAR STEEL Ø (In) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
POULTNEY WEST LS-5 (CONT.)																																			
24	STOP	1	30	30	6.25						1					X		X															RI-1	-	SHSM
26	COLLEGE CHURCH STOP	1	30	30	6.25		1 1				1					X		X															MOUNT SALVAGE SIGNS ABOVE STOP SIGN ON NEW SIGN POST 90° TO EACH OTHER RI-1	-	SHSM
27		1 1	30 24	30 12	6.25 2.00						1					X		X															WI1-2 (FLUORESCENT YELLOW-GREEN) WI6-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
28		1 1	30 24	30 12	6.25 2.00						1					X		X															WI1-2 (FLUORESCENT YELLOW-GREEN) WI6-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
30		1	36	36	4.50						1					X		X															RI-2	-	SHSM
32		1	36	36	4.50						1					X		X															RI-2	-	SHSM
33		1 1	30 24	30 12	6.25 2.00						1					X		X															WI1-2 (FLUORESCENT YELLOW-GREEN) WI6-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
34		1 1	30 24	30 12	6.25 2.00						1					X		X															WI1-2 (FLUORESCENT YELLOW-GREEN) WI6-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
35		1 1	30 24	30 12	6.25 2.00						1					X		X															WI1-2 (FLUORESCENT YELLOW-GREEN) WI6-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
36		1 1	30 24	30 12	6.25 2.00						1					X		X															WI1-2 (FLUORESCENT YELLOW-GREEN) WI6-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
37	STOP	1	30	30	6.25						1					X		X															RI-1	-	SHSM
38		1 1	30 24	30 12	6.25 2.00						1					X		X															WI1-2 (FLUORESCENT YELLOW-GREEN) WI6-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
39		1 1	30 24	30 12	6.25 2.00						1					X		X															WI1-2 (FLUORESCENT YELLOW-GREEN) WI6-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
												FT	FT	FT	FT	FT 195	FT		EA	LB	LB	LB		LB	LB	LB	LB								
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VAOT "SIGN POST DESIGN GUIDELINE."		TOTALS	SF 93.75	SF	EA. 2	SF						FT			FT 195					LB			EA.	LB				EA.	EA.	LB					

Stantec

PROJECT NAME: STATEWIDE SRTS PROJECTS
PROJECT NUMBER: STP SRIN(25)

FILE NAME: ...\09 Poultney West LS-5 TSS.dgn
PLOT DATE: 12/28/2012
PROJECT LEADER: G. GOYETTE
DRAWN BY: G. BURGMEIER
DESIGNED BY: STANTEC
CHECKED BY: G. GOYETTE
POULTNEY WEST TSS-7
SHEET 27 OF 35