STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 08

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (In)	SIGN DIMENSIONS HEIGHT (In)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (In) lb/ft 1.75	SQUARE STEEL (In) lb/ft 2.0	SQUARE STEEL (In) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0	TUBULAR ALUMINUM Ø (In) lb/ft 4.0	TUBULAR ALUMINUM Ø (In) lb/ft 4.0 MOD	FOUND-ATION	TUBULAR STEEL Ø (In) lb/ft 3.0	TUBULAR STEEL Ø (In) lb/ft 3.5	TUBULAR STEEL Ø (In) lb/ft 4.0	TUBULAR STEEL Ø (In) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
POULTNEY EAST LS-6																																				
2		1	30	30	6.25						1					X		X																WI1-2 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																													WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
4		1	30	30	6.25						1					X		X																WI1-2 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																													WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
5		1	30	30	6.25						1					X		X																WI1-2 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																													WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
6		1	30	30	6.25						1					X		X																WI1-2 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																													WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
7		1	30	30	6.25						1					X		X																WI1-2 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																													WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
9		1	30	30	6.25						1					X		X																WI1-2 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																													WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
11	SPEED LIMIT 25 / YOUR SPEED 29	1	24	30	-																													R2-1	-	SHSM
		1	30	42	-																													NEW SOLAR POWERED RSFS ASSEMBLY WITH POST AND BREAKAWAY FOUNDATION	-	SHSM
14	SPEED LIMIT 25 / YOUR SPEED 29	1	24	30	-																													R2-1	-	SHSM
		1	30	42	-																													NEW SOLAR POWERED RSFS ASSEMBLY WITH POST AND BREAKAWAY FOUNDATION	-	SHSM
19		1	36	36	9.00						2					X		X																SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																													WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
21	AHEAD	1	36	36	9.00						2					X		X																SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	30	18	3.75																													WI6-9P (FLUORESCENT YELLOW-GREEN)	-	SHSM
23		1	36	36	9.00						2					X		X																SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																													WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
25		1	36	36	9.00						2					X		X																SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																													WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
27	AHEAD	1	36	36	9.00						2					X		X																SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	30	18	3.75																													WI6-9P (FLUORESCENT YELLOW-GREEN)	-	SHSM
29		1	36	36	9.00						2					X		X																SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																													WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
												FT	FT	FT	FT	FT 270	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 119.00	SF	EA.	SF				FT			FT 270					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VAOT "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: STATEWIDE SRTS PROJECTS
PROJECT NUMBER: STP SRIN(25)

FILE NAME: ...\10 Poultney East LS-6 TSS.dgn PLOT DATE: 12/28/2012
PROJECT LEADER: G. GOYETTE DRAWN BY: G. BURGMEIER
DESIGNED BY: STANTEC CHECKED BY: G. GOYETTE
POULTNEY EAST TSS-8 SHEET 28 OF 35