STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 10

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (In)	SIGN DIMENSIONS HEIGHT (In)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (In) lb/ft 1.75	SQUARE STEEL (In) lb/ft 2.0	SQUARE STEEL (In) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0	TUBULAR ALUMINUM Ø (In) lb/ft 4.0	TUBULAR ALUMINUM Ø (In) lb/ft 4.0 MOD	FOUND-ATION	TUBULAR STEEL Ø (In) lb/ft 3.0	TUBULAR STEEL Ø (In) lb/ft 3.5	TUBULAR STEEL Ø (In) lb/ft 4.0	TUBULAR STEEL Ø (In) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
RUTLAND LS-8																																			
1		1	36	36	9.00						2					X		X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												W16-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
2		1	36	36	9.00						2					X		X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												W16-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
4		1	30	30	6.25						1					X		X															R1-1	-	SHSM
5		1	30	30	6.25						1					X		X															R1-1	-	SHSM
6		1	36	36	9.00						2					X		X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												W16-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
7		1	36	36	9.00						2					X		X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												W16-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
8		1	36	36	9.00						2					X		X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	8	1.33																												S4-3P (FLUORESCENT YELLOW-GREEN)	-	SHSM
12		1	24	8	1.33						1					X		X															S4-3P (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	30	5.00																												R2-1	-	SHSM
14		1	24	8	1.33						1					X		X															S4-3P (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	30	5.00																												R2-1	-	SHSM
16		1	36	36	9.00						2					X		X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	8	1.33																												S4-3P (FLUORESCENT YELLOW-GREEN)	-	SHSM
17		1	36	36	9.00						2					X		X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	8	1.33																												S4-3P (FLUORESCENT YELLOW-GREEN)	-	SHSM
18		1	36	36	9.00						2					X		X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	8	1.33																												S4-3P (FLUORESCENT YELLOW-GREEN)	-	SHSM
19		1	36	36	9.00						2					X		X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	8	1.33																												S4-3P (FLUORESCENT YELLOW-GREEN)	-	SHSM
												FT	FT	FT	FT	FT 330	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 120.81	SF	EA.	SF				FT			FT 330					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VAOT "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: STATEWIDE SRTS PROJECTS
PROJECT NUMBER: STP SRIN(25)

FILE NAME: ...\12 Rutland LS-8 TSS.dgn
PROJECT LEADER: G. GOYETTE
DESIGNED BY: STANTEC
RUTLAND TSS-10

PLOT DATE: 12/28/2012
DRAWN BY: G. BURGMEIER
CHECKED BY: G. GOYETTE
SHEET 30 OF 35