STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 12

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (In)	SIGN DIMENSIONS HEIGHT (In)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (In) lb/ft 1.75	SQUARE STEEL (In) lb/ft 2.0	SQUARE STEEL (In) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0	TUBULAR ALUMINUM Ø (In) lb/ft 4.0	TUBULAR ALUMINUM Ø (In) lb/ft 4.0 MOD	FOUND-ATION	TUBULAR STEEL Ø (In) lb/ft 3.0	TUBULAR STEEL Ø (In) lb/ft 3.5	TUBULAR STEEL Ø (In) lb/ft 4.0	TUBULAR STEEL Ø (In) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
WAITSFIELD LS-9																																				
2		1	24	30	-																													R2-1	-	SHSM
		1	24	21	-																													NEW SOLAR-POWERED RSFS ASSEMBLY WITH POST AND BREAKAWAY FOUNDATION	-	-
4		1	36	36	9.00						2					X		X																SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	36	12	3.00																													S4-3P (FLUORESCENT YELLOW-GREEN)	-	SHSM
6		1	24	30	-																													R2-1	-	SHSM
		1	24	21	-																													NEW SOLAR-POWERED RSFS ASSEMBLY WITH POST AND BREAKAWAY FOUNDATION	-	-
7		1	36	36	9.00						2					X		X																SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	36	12	3.00																													S4-3P (FLUORESCENT YELLOW-GREEN)	-	SHSM
8		1	24	30	-																													R2-1	-	SHSM
		1	24	21	-																													NEW SOLAR-POWERED RSFS ASSEMBLY WITH POST AND BREAKAWAY FOUNDATION	-	-
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VAOT "SIGN POST DESIGN GUIDELINE."												FT	FT	FT	FT	FT 60	FT		EA	LB	LB	LB		LB	LB	LB	LB								
	TOTALS				SF 24.00	SF	EA.	SF				FT			FT 60					LB			EA.	LB				EA.	EA.	LB					

PROJECT NAME: STATEWIDE SRTS PROJECTS
PROJECT NUMBER: STP SRIN(25)

FILE NAME: ...\13 Waitsfield LS-9 TSS.dgn
PROJECT LEADER: G. GOYETTE
DESIGNED BY: STANTEC
WAITSFIELD TSS-12

PLOT DATE: 12/28/2012
DRAWN BY: G. BURGMEIER
CHECKED BY: G. GOYETTE
SHEET 32 OF 35