STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 05

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 (1.88)	2.0 (2.42)	2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0 (1.3)	4.0 (1.7)	4.0 MOD (1.7)	TUBULAR STEEL Ø (In) FOUND-ATION	lb/ft 3.0 (7.6)	3.5 (9.0)	4.0 (10.8)	5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REFRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
NORTHFIELD LS-4																																			
1		1	36	36	9.00						2					X	28	X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	30	18	3.75																												S4-3P (FLUORESCENT YELLOW-GREEN)	-	SHSM
3		1	36	36	9.00						2					X	28	X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												W16-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
4		1	36	36	9.00						2					X	28	X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												W16-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
7		1	36	36	9.00						2					X	28	X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	30	18	3.75																												S4-3P (FLUORESCENT YELLOW-GREEN)	-	SHSM
TOTALS					SF 47.50	SF	EA.	SF				FT	FT	FT	FT	FT 120	FT		EA	LB	LB	LB		LB	LB	LB	LB								
												FT			FT ~~120~~ 112					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VAOT "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: STATEWIDE SRTS PROJECTS
PROJECT NUMBER: STP SRIN(25)

FILE NAME: ...\08 Northfield LS-4 TSS.dgn
PROJECT LEADER: G. GOYETTE
DESIGNED BY: STANTEC
NORTHFIELD TSS-5

PLOT DATE: 12/28/2012
DRAWN BY: G. BURGMEIER
CHECKED BY: G. GOYETTE
SHEET 25 OF 35