STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 07

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 (1.88)	2.0 (2.42)	2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0 (1.3)	4.0 (1.7)	4.0 MOD (1.7)	TUBULAR STEEL Ø (In) FOUND-ATION	lb/ft 3.0 (7.6)	3.5 (9.0)	4.0 (10.8)	5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
POULTNEY WEST LS-5 (CONT.)																																			
24	STOP	1	30	30	6.25						1					X	15	X															RI-1	-	SHSM
26	COLLEGE CHURCH STOP	1	30	30	6.25		1 1				1					X	15	X															MOUNT SALVAGE SIGNS ABOVE STOP SIGN ON NEW SIGN POST 90° TO EACH OTHER RI-1	-	SHSM
27		1 1	30 24	30 12	6.25 2.00						1					X	15	X															W11-2 (FLUORESCENT YELLOW-GREEN) W16-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
28		1 1	30 24	30 12	6.25 2.00						1					X	15	X															W11-2 (FLUORESCENT YELLOW-GREEN) W16-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
30		1	36	36	4.50						1					X	15	X															RI-2	-	SHSM
32		1	36	36	4.50						1					X	15	X															RI-2	-	SHSM
33		1 1	30 24	30 12	6.25 2.00						1					X	15	X															W11-2 (FLUORESCENT YELLOW-GREEN) W16-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
34		1 1	30 24	30 12	6.25 2.00						1					X	15	X															W11-2 (FLUORESCENT YELLOW-GREEN) W16-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
35		1 1	30 24	30 12	6.25 2.00						1					X	15	X															W11-2 (FLUORESCENT YELLOW-GREEN) W16-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
36		1 1	30 24	30 12	6.25 2.00						1					X	15	X															W11-2 (FLUORESCENT YELLOW-GREEN) W16-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
37	STOP	1	30	30	6.25						1					X	15	X															RI-1	-	SHSM
38		1 1	30 24	30 12	6.25 2.00						1					X	15	X															W11-2 (FLUORESCENT YELLOW-GREEN) W16-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
39		1 1	30 24	30 12	6.25 2.00						1					X	15	X															W11-2 (FLUORESCENT YELLOW-GREEN) W16-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
												FT	FT	FT	FT	FT 195	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 93.75	SF	EA. 2	SF				FT			FT 195					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VAOT "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: STATEWIDE SRTS PROJECTS
PROJECT NUMBER: STP SRIN(25)
FILE NAME: ...\09 Poultney West LS-5 TSS.dgn PLOT DATE: 12/28/2012
PROJECT LEADER: G. GOYETTE DRAWN BY: G. BURGMEIER
DESIGNED BY: STANTEC CHECKED BY: G. GOYETTE
POULTNEY WEST TSS-7 SHEET 27 OF 35