STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 08

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 (1.88)	2.0 (2.42)	2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0 (1.3)	4.0 (1.7)	4.0 MOD (1.7)	TUBULAR STEEL Ø (In) lb/ft FOUND-ATION	3.0 (7.6)	3.5 (9.0)	4.0 (10.8)	5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
POULTNEY EAST LS-6																																			
2		1	30	30	6.25						1					X	12	X															WI1-2 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
4		1	30	30	6.25						1					X	12	X															WI1-2 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
5		1	30	30	6.25						1					X	12	X															WI1-2 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
6		1	30	30	6.25						1					X	12	X															WI1-2 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
7		1	30	30	6.25						1					X	12	X															WI1-2 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
9		1	30	30	6.25						1					X	12	X															WI1-2 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
11	SPEED LIMIT 25	1	24	30	-																												R2-1	-	SHSM
	YOUR SPEED 29	1	30	42	-																												NEW SOLAR POWERED RSFS ASSEMBLY WITH POST AND BREAKAWAY FOUNDATION	-	SHSM
14	SPEED LIMIT 25	1	24	30	-																												R2-1	-	SHSM
	YOUR SPEED 29	1	30	42	-																												NEW SOLAR POWERED RSFS ASSEMBLY WITH POST AND BREAKAWAY FOUNDATION	-	SHSM
19		1	36	36	~~9.00~~						~~2~~					~~X~~		~~X~~															~~SI-1 (FLUORESCENT YELLOW-GREEN)~~	-	SHSM
		1	24	12	~~2.00~~																												~~WI6-7p (FLUORESCENT YELLOW-GREEN)~~	-	SHSM
21	AHEAD	1	36	36	9.00						2					X	30	X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	30	18	3.75																												WI6-9P (FLUORESCENT YELLOW-GREEN)	-	SHSM
23		1	36	36	9.00						2					X	30	X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
25		1	36	36	9.00						2					X	30	X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	2.00																												WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
27	AHEAD	1	36	36	9.00						2					X	30	X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	30	18	3.75																												WI6-9P (FLUORESCENT YELLOW-GREEN)	-	SHSM
29		1	36	36	~~9.00~~						2					X	30	X															SI-1 (FLUORESCENT YELLOW-GREEN)	-	SHSM
		1	24	12	~~2.00~~																												WI6-7p (FLUORESCENT YELLOW-GREEN)	-	SHSM
												FT	FT	FT	FT	FT ~~270~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 97 ~~119.00~~	SF	EA.	SF				FT			FT 222 ~~270~~					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VAOT "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: STATEWIDE SRTS PROJECTS
PROJECT NUMBER: STP SRIN(25)

FILE NAME: ...\10 Poultney East LS-6 TSS.dgn
PLOT DATE: 12/28/2012
PROJECT LEADER: G. GOYETTE
DRAWN BY: G. BURGMEIER
DESIGNED BY: STANTEC
CHECKED BY: G. GOYETTE
POULTNEY EAST TSS-8
SHEET 28 OF 35