STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 10

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 (1.88)	2.0 (2.42)	2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0 (1.3)	4.0 (1.7)	4.0 MOD (1.7)	TUBULAR STEEL Ø (In) lb/ft FOUND-ATION	3.0 (7.6)	3.5 (9.0)	4.0 (10.8)	5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
RUTLAND LS-8																																			
1		1 1	36 24	36 12	9.00 2.00						2					28 X		X															SI-1 (FLUORESCENT YELLOW-GREEN) W16-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
2		1 1	36 24	36 12	9.00 2.00						2					28 X		X															SI-1 (FLUORESCENT YELLOW-GREEN) W16-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
4	STOP	1	30	30	6.25						1					12 X		X															R1-1	-	SHSM
5	STOP	1	30	30	6.25						1					12 X		X															R1-1	-	SHSM
6		1 1	36 24	36 12	9.00 2.00						2					28 X		X															SI-1 (FLUORESCENT YELLOW-GREEN) W16-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
7		1 1	36 24	36 12	9.00 2.00						2					28 X		X															SI-1 (FLUORESCENT YELLOW-GREEN) W16-7p (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
8	SCHOOL	1 1	36 24	36 8	9.00 1.33						2					28 X		X															SI-1 (FLUORESCENT YELLOW-GREEN) S4-3P (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
12	SCHOOL SPEED LIMIT 25	1 1	24 24	8 30	1.33 5.00						1					12 X		X															S4-3P (FLUORESCENT YELLOW-GREEN) R2-1	- -	SHSM SHSM
14	SCHOOL SPEED LIMIT 25	1 1	24 24	8 30	1.33 5.00						1					12 X		X															S4-3P (FLUORESCENT YELLOW-GREEN) R2-1	- -	SHSM SHSM
16	SCHOOL	1 1	36 24	36 8	9.00 1.33						2					28 X		X															SI-1 (FLUORESCENT YELLOW-GREEN) S4-3P (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
17	SCHOOL	1 1	36 24	36 8	9.00 1.33						2					24 X		X															SI-1 (FLUORESCENT YELLOW-GREEN) S4-3P (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
18	SCHOOL	1 1	36 24	36 8	9.00 1.33						2					24 X		X															SI-1 (FLUORESCENT YELLOW-GREEN) S4-3P (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
19	SCHOOL	1 1	36 24	36 8	9.00 1.33						2					24 X		X															SI-1 (FLUORESCENT YELLOW-GREEN) S4-3P (FLUORESCENT YELLOW-GREEN)	- -	SHSM SHSM
												FT	FT	FT	FT	FT ~~330~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 120.81	SF	EA.	SF				FT			FT 288 ~~330~~					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VAOT "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: STATEWIDE SRTS PROJECTS
PROJECT NUMBER: STP SRIN(25)

FILE NAME: ...\12 Rutland LS-8 TSS.dgn
PROJECT LEADER: G. GOYETTE
DESIGNED BY: STANTEC
RUTLAND TSS-10

PLOT DATE: 12/28/2012
DRAWN BY: G. BURGMEIER
CHECKED BY: G. GOYETTE
SHEET 30 OF 35