

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	LANDSCAPING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)
						1					1		LS	MOBILIZATION/DEMobilIZATION	635.11		148	TONS	TYPE IVS - WEARING COURSE
						1					1		LS	TRAFFIC CONTROL	641.10		130	TONS	TYPE IIS - BASE COURSE
									1010		1010		SY	GEOTEXTILE UNDER STONE FILL	649.31		278	TONS	TOTAL
								300			300		SY	GEOTEXTILE FOR SILT FENCE	649.51				DRIVES
								300			300		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61		12	TONS	STA. 102+55, LT
								10			10		LB	SEED	651.15		20	TONS	STA. 103+60, RT
								70			70		LB	FERTILIZER	651.18		32	TONS	TOTAL
								0.3			0.3		TON	AGRICULTURAL LIMESTONE	651.20				TOTAL BIT. CONCRETE PAVEMENT, SMALL QUANTITY
								0.3			0.3		TON	HAY MULCH	651.25				
								40			40		CY	TOPSOIL	651.35				
								300			300		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								80			80		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								110			110		SY	TEMPORARY EROSION MATTING	653.20				
								15			15		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
								30			30		CY	VEHICLE TRACKING PAD	653.35				
								70			70		LF	BARRIER FENCE	653.50				
								650			650		LF	PROJECT DEMARCATION FENCE	653.55				
							7				7		EACH	DECIDUOUS TREES (ACER RUBRUM) (B&B) (2.5" - 3" DIA.)	656.30				
							6				6		EACH	DECIDUOUS TREES (ACER SACCHARINUM) (B&B) (2" - 2.5" DIA.)	656.30				
							58				58		EACH	DECIDUOUS SHRUBS (CORNUS SERICEA) (B&B) (36" - 48" HT.)	656.35				
							7.2				7.2		MGAL	LANDSCAPE WATERING	656.65				
							65				65		CY	LANDSCAPE BACKFILL, TRUCK MEASUREMENT	656.80				
							1				1		LS	TREE PROTECTION	656.85				
						12					12		SF	TRAFFIC SIGNS, TYPE A	675.20				
						30					30		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
						11					11		EACH	REMOVING SIGNS	675.50				
						1					1		EACH	ERECTING SALVAGED SIGNS	675.60				
									200		200		LF	SPECIAL PROVISION (BRIDGE RAILING, GALVANIZED HDSB/FASCIA MOUNTED/STEEL TUBING)	900.640				
						175					175		LF	SPECIAL PROVISION (FABRIC SCREENING FENCE)	900.640				
									96		96		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE NON-VOIDED SLABS)(18"x36")	900.640				
									240		240		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE NON-VOIDED SLABS)(18"x48")	900.640				
						1					1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650				
						1					1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650				
						310					310		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME: BRATTLEBORO

PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10J062qs.dgn

PROJECT LEADER: S.E. BURBANK

DESIGNED BY: E.A. FIALA

QUANTITY SHEET #2

PLOT DATE: 11/12/2013

DRAWN BY: A.J. GOUDREAU

CHECKED BY: S.E. BURBANK

SHEET 9 OF 68

