



NOTE:
 NF = NEAR FACE
 FF = FAR FACE
 EF = EACH FACE
 ▲ = CUT TO FIT IN FIELD
 3" CLEAR, UNLESS OTHERWISE SPECIFIED ON THE PLANS.
 2'-2" BAR LAP UNLESS OTHERWISE SPECIFIED ON THE PLANS.

*** JOINT IS TO BE LOCATED ACCURATELY BY STRING LINING, OR OTHER MEANS, PRIOR TO PAVING, SO THAT THE SAW CUTS WILL BE MADE DIRECTLY OVER THE END OF THE APPROACH SLAB. JOINT SHALL BE CUT DRY IN A SINGLE PASS AND BE SEALED WITHIN 24 HOURS OR PRIOR TO EXPOSURE TO TRAFFIC. JOINT SHALL BE CLEANED PRIOR TO APPLYING THE JOINT SEALER.

PROJECT NAME:	BRATTLEBORO	FILE NAME:	z10j062sup04.dgn	PLOT DATE:	10/14/2013
PROJECT NUMBER:	BRO 1442(35)	PROJECT LEADER:	S.E. BURBANK	DRAWN BY:	J.L. LEMIEUX
		DESIGNED BY:	S.E. BURBANK	CHECKED BY:	S.E. BURBANK
		APPROACH SLAB DETAILS		SHEET	40 OF 68

