NOTES:

1. THESE PLANS SHOW A CONCEPTUAL EROSION CONTROL PLAN, THE CONTRACTOR MUST SUBMIT A TEMPORARY EROSION CONTROL PLAN FOR APPROVAL. THE CONTRACTOR MAY RELOCATE TEMPORARY MEASURES TO IMPROVE EROSION CONTROL WITH APPROVAL OF THE RESIDENT ENGINEER.
2. SILT FENCE SHALL NOT BE INSTALLED ACROSS CONTOURS.
3. THE CONTRACTOR SHALL USE OTHER TEMPORARY EROSION CONTROL MEASURES AS NECESSITATED BY THE SEQUENCE OF CONSTRUCTION OR AS DIRECTED BY THE RESIDENT ENGINEER.
4. REFER TO TEMPORARY EROSION CONTROL DETAIL SHEETS FOR ADDITIONAL DETAILS.
5. WHERE LEDGE IS EXPOSED, GRAVEL BAGS MAY BE USED INSTEAD OF FILTER CURTAIN. PAYMENT FOR GRAVEL BAGS WOULD BE INCLUDED FOR PAYMENT UNDER THE UNIT PRICE BID FOR ITEM 649.61 "GEOTEXTILE FOR FILTER CURTAIN".

SOIL CLASSIFICATION

BERKSHIRE AND MANADNOCK FINE SANDY LOAM (IIC)
8% TO 15% SLOPES
"K FACTOR" 0.24
CLASSIFIED MODERATE EROSION POTENTIAL

SOIL CLASSIFICATION

BERKSHIRE AND MANADNOCK FINE SANDY LOAM (IIC)
8% TO 15% SLOPES
"K FACTOR" 0.24
CLASSIFIED MODERATE EROSION POTENTIAL

NOTE: SEE EROSION CONTROL DETAILS FOR SYMBOLOGY.

VHB Vanasse Hangen Brustlin, Inc.

PROJECT NAME: GUILFORD
PROJECT NUMBER: BRO 1442(36)

FILE NAME: z10j064bdr_ero.dgn
PROJECT LEADER: S.E. BURBANK
DESIGNED BY: S.E. BURBANK
EPSC CONSTRUCTION CONDITIONS PLAN

PLOT DATE: 10/2/2013
DRAWN BY: E.A. FIALA
CHECKED BY: S.E. BURBANK
SHEET 39 OF 42

VHB 57427