

Submittal Notes

Rev #1 (To be used when reviewing shop drawing submittal)

New Haven – River Road Bridge #10 – Project BRF 0183 (1)

1. Reference drawing PC1

We increased concrete strength to 5,000 psi to allow for a decrease in lap length. Note minimum lap length of 2'-6".

2. Reference drawing WW1, Detail "B"

We have substituted a keyway for the "roughened surface" called out on the contract drawings.

3. Reference drawings F5 & PC1 and RFI 002

Please note approved change to location of #11 rebar and #6 rebar.

The current steel shop drawings do not reflect this change.

Hole size for #11 bar increased to 2.5" dia. – rev. #1

Location for (6) vertical # 6 bars changes – rev. #1