STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 – BARRE TOWN 1 (DONAHUE RD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 1.100, RT	A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 52 FT NORTH OF LOWERY RD ABOVE THE NEW SPEED LIMIT SIGN		7	
		A	R2-1	24	30		SPEED LIMIT 40 / SPEED LIMIT 35	5.00																		INSTALL NEW SIGN BELOW THE LEGAL LOAD SIGN AT 52 FT NORTH OF LOWERY RD ON THE SAME POST	X		
NB	MM 1.120, RT	A	R2-1	24	30		SPEED LIMIT 40						X		X											REMOVE SIGN AND POST			
SB	MM 1.190, LT	F	W2-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 25 FT SOUTH OF POLE# GMP/14/13 1/2	X		
		F	W16-8aP	48	15		[redacted]	5.00																		INSTALL NEW SIGN BENEATH THE INTERSECTION WARNING SIGN AT THE CORRECT SIGN HEIGHT		8	
NB	MM 1.250, RT	A	W3-5	36	36		SPEED LIMIT 25	9.00								2		X								INSTALL SIGN ON 2-POSTS ACROSS FROM POLE# 12 3/4	X		
NB	MM 1.280, RT	A	W1-2L	30	30								X		X											REMOVE SIGN AND POST			
NB	MM 1.290, RT	A	W10-1L	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS AT POLE# 12 1/2	X		
NB	MM 1.320, RT	A	R2-1	24	30		SPEED LIMIT 25	5.00								1		X								INSTALL NEW SIGN AND POST 79 FT SOUTH OF POLE # 12A	X		
SB	MM 1.320, LT	E	R2-1	24	30		SPEED LIMIT 25	5.00								1		X								INSTALL NEW SIGN AND POST 79 FT SOUTH AND OPPOSITE OF POLE # 12A	X		
		F	R2-1	24	30		SPEED LIMIT 40 / SPEED LIMIT 35	5.00																		INSTALL NEW SIGN ON BACKSIDE OF SPEED LIMIT 25 SIGN AT 79 FT SOUTH AND OPPOSITE OF POLE# 12A ON THE SAME POST	X		
NB	MM 1.340, RT	A B	W1-8 L W1-8 R	18 18	24 24		B-B	3.00 3.00								1		X								INSTALL NEW CHEVRONS BACK-TO-BACK ON A SIGN BRACKET AND A SINGLE POST 25 FT NORTH OF POLE# 12A	X X		
NB	MM 1.355, RT	A B	W1-8 L W1-8 R	18 18	24 24		B-B	3.00 3.00								1		X								INSTALL NEW CHEVRONS BACK-TO-BACK ON A SIGN BRACKET AND A SINGLE POST 105 FT NORTH OF POLE# 12A	X X		
NB	MM 1.370, RT	A B	W1-8 L W1-8 R	18 18	24 24		B-B	3.00 3.00								1		X								INSTALL NEW CHEVRONS BACK-TO-BACK ON A SIGN BRACKET AND A SINGLE POST 185 FT NORTH OF POLE# 12A	X X		
NB	MM 1.380, RT	A	R2-1	24	30		SPEED LIMIT 25						X		X											REMOVE SIGN AND POST			
							SHEET SUBTOTALS	SF 75.00	SF	EA 4			EA 4	EA 4		EA 12	FT 180			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARRE TOWN (1) TSS SHEET 3
PLOT DATE: 13-SEP-2012 15:46
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 15 OF 64