STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4 – BARRE TOWN 1 (DONAHUE RD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 1.380, LT	E	R2-1	24	30		SPEED LIMIT 25						X		X											REMOVE SIGN AND POST			
		F	R2-1	24	30		~~SPEED LIMIT 40~~						X													REMOVE SIGN			
NB	MM 1.390, RT	D	R2-1	30	30		STOP	6.25					X		X	1		X								INSTALL NEW SIGN AND POST AT THE SAME LOCATION (WATERMAN FARM RD)	X		
NB	MM 1.400, RT	A	W6-1	48	24		B-B	8.00								2		X								INSTALL 2 LARGE ARROWS BACK-TO-BACK 5 FT APART 158 FT SOUTH OF POLE# GMP/10/7-7. INSTALL THE ONE FACING NORTHBOUND TRAFFIC AT A HEIGHT THAT ALLOWS IT TO BE SEEN BY NORTHBOUND DRIVERS WHEN THEY APPROACH FROM WATERMAN FARM RD	X		
		B						8.00								2		X									X		
SB	MM 1.430, LT	F	W1-2R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST OPPOSITE POLE# GMP/10/7-7	X		
NB	MM 1.450, RT	A	W1-2MbR	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 105 FT NORTH OF POLE# GMP/10/7-7		10	
SB	MM 1.570, LT	F	W1-2L	30	30			6.25								1		X								INSTALL NEW SIGN AND POSTS OPPOSITE PANTHER RD	X		
NB	MM 1.590, RT	A	R2-1	24	30		SPEED LIMIT 25	5.00								1		X								INSTALL NEW SIGN AND POST 105 FT NORTH OF PANTHER RD	X		
NB	MM 1.760, RT	A	W10-1R	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 15 FT SOUTH OF POLE# 2/GMP/2	X		
		A	W16-8P	36	8		Websterville Rd	2.00																		INSTALL NEW SIGN BENEATH THE CURVE/INTERSECTION WARNING SIGN AT THE CORRECT SIGN HEIGHT		8	
NB	MM 1.780, LT	F	R2-1	24	30		SPEED LIMIT 25						X		X											REMOVE SIGN AND POST			
NB	MM 1.800, LT	F	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS NEW	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 200 FT NORTH OF AND OPPOSITE POLE# 2/GMP/2		7	
		F	R2-1	24	30		SPEED LIMIT 25	5.00																		INSTALL NEW SIGN BENEATH THE LEGAL LOAD SIGN ON THE SAME POST	X		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED
						EA 5		EA 4										
SHEET SUBTOTALS	SF 67.00	SF				EA 5		EA 4	EA 12		FT 180		EA				LB	

PROJECT NAME:	STATEWIDE NORTHEAST REGION
PROJECT NUMBER:	STP HRRR(4)
FILE NAME: 10k016_wrk.dgn	PLOT DATE: 13-SEP-2012 15:46
PROJECT LEADER: JLS	DRAWN BY: ITS
DESIGNED BY: NLA	CHECKED BY: JLS
BARRE TOWN (1) TSS SHEET 4	SHEET 16 OF 64