STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 – BARRE TOWN 2 (OSBORNE RD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
SB	MM 0.730, LT	F	W1-2R	30	30			6.25								I		X								INSTALL NEW SIGN AND POST 725 FT SOUTH OF POLE# GMP/21/58	X		
SB	MM 0.860, LT	F	R2-1	24	30			5.00								I		X								INSTALL NEW SIGN AND POST 40 FT SOUTH OF POLE# GMP/21/58	X		
NB	MM 0.860, RT	A	R2-1	24	30			5.00								I		X								INSTALL NEW SIGN AND POST 40 FT SOUTH OF AND OPPOSITE POLE# GMP/21/58 ACROSS THE ROAD FROM THE OTHER SPEED LIMIT 40 SIGN ASSEMBLY	X		
SB	MM 0.903, LT	F	W1-2L	30	30			6.25					X		X	2		X								INSTALL NEW SIGN ON 2-POSTS 1753 FT SOUTH OF THE CENTER OF THE PHELPS ROAD INTERSECTION	X		
		F	S3-1	30	30	F-Y-G		6.25					X													INSTALL NEW SIGN BENEATH CURVE LEFT WARNING SIGN ON THE SAME POSTS AT THE CORRECT SIGN HEIGHT	X		
NB	MM 1.140, RT	A	W2-1	36	36			9.00					X		X	2		X								INSTALL NEW SIGN ON 2-POSTS 500 FT SOUTH OF PHELPS RD	X		
		A	W16-8P	30	8		Phelps Rd	1.67																		INSTALL NEW SIGN BENEATH INTERSECTION WARNING SIGN AT THE CORRECT SIGN HEIGHT		8	
SB	MM 1.190, LT	F	R2-1	24	30			5.00					X		X	1		X								INSTALL NEW SIGN AND POST 200 FT SOUTH OF PHELPS RD	X		
SB	MM 1.230, LT	G/H	D3-1	36	12		Osborne Rd	3.00					X		X	1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION SOUTH OF THE STOP SIGN (PHELPS RD)		8	
		H	R1-1	30	30			6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL STOP SIGN AND POST AT SAME LOCATION (WEST APPROACH OF PHELPS RD)	X		
NB	MM 1.230, RT	D	R1-1	30	30			6.25								1		X								INSTALL NEW STOP SIGN AND POST ON THE LEFT HAND SIDE OF THE EAST APPROACH OF PHELPS RD	X		
SB	MM 1.230, LT +250 FT	H	W2-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 225 FT WEST OF OSBORNE RD ON PHELPS RD	X		
		H	W16-8aP	48	15		← Cutler Corner Rd Osborne Rd →	5.00																		INSTALL NEW SIGN BENEATH INTERSECTION WARNING SIGN AT THE CORRECT SIGN HEIGHT		8	
NB	MM 1.240, RT	D	R1-1	30	30			6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL STOP SIGN AND POST AT SAME LOCATION (RIGHT HAND SIDE OF THE EAST APPROACH OF PHELPS RD)	X		
							SHEET SUBTOTALS	SF 80.17	SF	EA 7				EA 6		EA 14	FT 210			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARRE TOWN (2) TSS SHEET 2
PLOT DATE: 13-SEP-2012 15:47
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 19 OF 64