STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 – BARRE TOWN 2 (OSBORNE RD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
SB	MM 1.240, LT	F/E	D3-1	36	12		[redacted]	3.00					X		X											INSTALL NEW SIGN ABOVE THE CUTLER CORNER SIGN AT SAME LOCATION - NORTHWEST CORNER OF PHELPS RD		8	
		G/H	D3-1	54	12		[redacted]	4.50					X			2		X								INSTALL NEW SIGN ON 2-POSTS AT THE NORTHWEST CORNER OF PHELPS RD		8	
NB	MM 1.240, RT +250 FT	D	W2-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 225 FT EAST OF CUTLER CORNER RD ON PHELPS RD	X		
		D	W16-8aP	48	15		← Osborne Rd Cutler Corner Rd →	5.00																		INSTALL NEW SIGN BENEATH THE INTERSECTION WARNING SIGN AT THE CORRECT SIGN HEIGHT		8	
NB	MM 1.280, RT	A	R2-1	24	30		SPEED LIMIT 40 / SPEED LIMIT 35	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 237 FT NORTH OF PHELPS RD	X		
SB	MM 1.300, LT	F	W2-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 343 FT NORTH OF PHELPS RD	X		
		F	W16-8P	30	8		Phelps Rd	1.67																		INSTALL NEW SIGN BENEATH THE INTERSECTION WARNING SIGN AT THE CORRECT SIGN HEIGHT		8	
NB	MM 1.770, RT	A	W1-2L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 158 FT SOUTH OF POLE # 6/80	X		
NB	MM 1.831, RT TO MM 1.890, RT	A B		6	8		(10) TYPE II - 6" X 8" WHITE DELINEATORS	3.33								5	X									INSTALL DELINEATORS BACK-TO-BACK (10 TOTAL) 70 FT APART GOING SOUTH. INSTALL THE FIRST ONE AT POLE # NET/82		7	
NB	MM 2.142, RT TO MM 2.208, RT	A B		6	8		(12) TYPE II - 6" X 8" WHITE DELINEATORS	4.00								6	X									INSTALL DELINEATORS BACK-TO-BACK (12 TOTAL) 70 FT APART IN THE AREA OF THE POND GOING NORTH. INSTALL THE FIRST ONE AT POLE # NET/82		7	
SB	MM 2.270, LT	F	S3-1	30	30	F-Y-G-	SCHOOL BUS STOP AHEAD	6.25					X		X	1		X								INSTALL NEW SIGN AND POST 2481FT NORTH OF POLE# 6/80	X		
SB	MM 2.670, LT	F	VW-060	30	30		HIDDEN DRIVES	6.25								1		X								INSTALL NEW SIGN AND POST ACROSS THE ROAD FROM THE AT END OF FENCE LINE		8	
SB	MM 2.730, LT	F	W11-7	30	30			6.25					X		X	1		X								INSTALL NEW SIGN AND POST 158 FT SOUTH OF LADD RD	X		
		F	W7-3aP	24	18		NEXT 1½ MILES	3.00					X													INSTALL NEW SIGN BENEATH THE EQUESTRIAN SYMBOL SIGN AT THE CORRECT SIGN HEIGHT	X		
							SHEET SUBTOTALS	SF 72.50	SF	EA 6				EA 4		EA 22	FT 253			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARRE TOWN (2) TSS SHEET 3
PLOT DATE: 13-SEP-2012 15:47
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 20 OF 64