
















TRAFFIC SIGN SUMMARY SHEET 2 - BARRE TOWN 3 (BRIDGE ST)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL		
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		FOUNDATION			lb/ft						DETAIL IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
																	1.75	2.00	2.50	3.00	3.50	4.00	5.00					
EB	MM 0.165, RT	A	W3-1	30	30							X		X										REMOVE STOP AHEAD SIGN AND POST (147 FT NORTH OF POLE 3 5/9-2/5)				
		A	W11-1	30	30			6.25							1		X							INSTALL NEW BIKE SIGN AND POST 147 FT NORTH OF POLE 3 5/9-2/5	X			
		A	W16-IP	18	24			3.00																INSTALL NEW SIGN BENEATH BICYCLE SYMBOL WARNING SIGN ON THE SAME POST AT THE CORRECT SIGN HEIGHT	X			
EB	MM 0.183, RT	A	W11-1	30	30							X		X										REMOVE SIGN AND POST				
EB	MM 0.206, RT	A	W1-4 L	30	30			6.25							1		X							INSTALL NEW SIGN AND POST 31FT EAST OF AND ACROSS FROM POLE# 9/7	X			
EB	MM 0.306, RT	A	W6-1	48	24		 TWO SIGNS	16.00 8.00							2		X							INSTALL NEW SIGN ON 2-POSTS 10 FT NORTH OF POLE 12/9-2/10/75930 AT RIGHT ANGLES TO APPROACHING TRAFFIC	X			
EB	MM 0.263, RT TO MM 0.345, RT	A B		6	8		(14) TYPE II - 6" X 8" WHITE DELINEATORS	4.67							7	X								INSTALL DELINEATORS BACK-TO-BACK AT 60 FT SPACING GOING EAST. INSTALL FIRST SET ACROSS FROM POLE# 13/11/75931		7		
EB	MM 0.385, RT	A	W1-IL	30	30			6.25							1		X							INSTALL NEW SIGN AND POST ACROSS FROM POLE# 14/12/75934	X			
EB	MM 0.566, RT	A	R2-1	24	30			5.00				X		X	1		X							INSTALL NEW SIGN AND POST 42 FT WEST OF POLE# 22/17	X			
WB	MM 0.566, LT	E	R2-1	24	30			5.00				X		X	1		X							REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT 42 FT WEST OF AND ACROSS FROM POLE# 22/17	X			
WB	MM 0.613, LT	H	RI-1	30	30			6.25				X		X	1		X							REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT SAME LOCATION (ALLEN ST)	X			
WB	MM 0.622, LT	F	R2-1	24	30			5.00							1		X							INSTALL NEW SIGN AND POST 58 FT WEST OF AND ACROSS FROM POLE# 28/40/44	X			
EB	MM 0.637, RT	A	W3-5	24	30							X		X										REMOVE SIGN AND POST				
EB	MM 0.637, RT LT	A	W3-5	36	36		 	18.00 9.00							2		X							INSTALL NEW SIGN ON 2-POSTS 137 FT WEST OF AND POLE# 28/40/44	X			
EB	MM 0.724, RT	D	RI-1	30	30						X			X										RETAIN SIGN AND POST (LOWER USLER RD)	X			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

SHEET SUBTOTALS

SF
~~64.67~~
81.67

EA EA EA EA EA EA
1 6 1 6

FT FT FT
56 165

LB LB LB LB

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARRE TOWN (3) TSS SHEET 2

PLOT DATE: 13-SEP-2012 15:47
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 24 OF 64