STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 – BARRE TOWN 4 (WEBSTERVILLE RD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 1.144, LT	F	D1-1	72	12		↑ Graniteville	6.00								2		X								INSTALL NEW SIGN ON 2-POSTS 26 FT NORTH OF AND ACROSS FROM POLE# 49		9	
		F	D1-1	72	12		← Websterville	6.00																		INSTALL NEW SIGN BENEATH GRANITEVILLE DESTINATION SIGN ON THE SAME POSTS		9	
		F	D1-1	72	12		← East Barre	6.00																		INSTALL NEW SIGN BENEATH WEBSTERVILLE DESTINATION SIGN ON THE SAME POSTS		9	
SB	MM 1.182, LT	F	W2-1	36	36			9.00								2		X								INSTALL SIGN ON 2-POSTS 42 FT SOUTH OF AND ACROSS FROM POLE# 41	X		
		F	W16-8aP	48	15		← Websterville Rd Sterling Hill Rd →	5.00																		INSTALL NEW SIGN BENEATH INTERSECTION WARNING SIGN AT THE CORRECT SIGN HEIGHT		9	
							WEBSTERVILLE ROAD																						
EB	MM 0.023, RT	A	VW-079	24	30		LEGAL LOAD AS FOR STATE HIGHWAYS	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 63 FT WEST OF AND ACROSS FROM POLE# 56/57		7	
		A	R2-1	24	30		SPEED LIMIT 30 SPEED LIMIT 35	5.00																		INSTALL NEW SIGN BENEATH LEGAL LOAD LIMIT SIGN ON SAME POST	X		
WB	MM 0.070, LT	F	D1-1	72	12		← Graniteville	6.00								2		X								INSTALL SIGN ON 2-POSTS 30 FT WEST OF POLE# GMP/55/58		9	
		F	D1-1	72	12		Barre →	6.00																		INSTALL NEW SIGN BENEATH GRANITEVILLE DESTINATION SIGN ON THE SAME POSTS		9	
EB	MM 0.117, RT	A	S1-1	30	30								X		X											REMOVE SIGN AND POST			
WB	MM 0.121, LT	F	R3-1	36	36			9.00					X		X	2		X								INSTALL NEW SIGN ON 2-POSTS 36 FT EAST OF POLE# GMP/54/59	X		
EB	MM 0.132, RT	A	S1-1	30	30	F-Y-G		6.25								1		X								INSTALL SIGN AND POST 95 FT WEST OF POLE# 3/324/60/53385	X		
		A	W16-9P	24	12	F-Y-G	AHEAD	2.00																		INSTALL NEW SIGN BENEATH SCHOOL ZONE SYMBOL WARNING SIGN ON THE SAME POST AT THE CORRECT SIGN HEIGHT	X		
										EA	EA	EA	EA 3	EA	EA 3		FT	FT 150	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 71.25	SF	EA 3				EA 3		EA 10	FT 150			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARRE TOWN (4) TSS SHEET 2
PLOT DATE: 13-SEP-2012 15:47
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 28 OF 64