















TRAFFIC SIGN SUMMARY SHEET 5 - BARRE TOWN 4

(WEBSTERVILLE RD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL		
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		FOUNDATION			lb/ft						DETAIL IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
																	1.75	2.00	2.50	3.00	3.50	4.00	5.00					
WB	MM 1.291, LT	F	R2-2	24	30			5.00					X		X	1		X						INSTALL NEW SIGN AND POST 84 FT WEST OF THE CENTER OF WEBSTERVILLE RD/CHURCHILL RD INTERSECTION	X			
EB	MM 1.298, RT	A	M4-5	24	12			2.00								1		X						INSTALL NEW SIGN AND POST 48 FT WEST OF THE CENTER OF WEBSTERVILLE RD/CHURCHILL RD INTERSECTION			E-136B	
		A	MI-5	30	24			5.00																INSTALL NEW SIGN BENEATH TO AUXILIARY SIGN ON THE SAME POST			E-136B	
		A	M6-1	21	15			2.19																INSTALL NEW SIGN BENEATH STATE ROUTE MARKER ON SAME POST			E-136B	
		A	M4-5	24	12			2.00																INSTALL NEW SIGN AND POST DIRECTLY NEXT TO BUT NOT TOUCHING THE PREVIOUS SIGN ASSEMBLY	X			
		A	MI-4	30	24			5.00																INSTALL NEW SIGN BENEATH TO AUXILIARY SIGN ON THE SAME POST	X			
		A	M6-1	21	15			2.19																INSTALL NEW SIGN BENEATH US ROUTE MARKER ON SAME POST	X			
WB	MM 1.315, LT	F	RI-2	36	36			3.89					X	X										REMOVE SIGN AND INSTALL NEW SIGN ON SAME POST (WEBSTERVILLE RD/ CHURCH HILL RD INTERSECTION)	X			
		G/H	D3-1	42	6							X	X											SALVAGE SIGN AND INSTALL ABOVE THE YIELD SIGN				
EB	MM 1.327, RT	A	R2-1	24	30			5.00								1		X						INSTALL NEW SIGN AND POST 105 FT EAST OF THE CENTER OF WEBSTERVILLE RD/CHURCHILL RD INTERSECTION	X			
EB	MM 1.359, RT	A	S3-1	30	30	F-Y-G		6.25					X	X	1			X						REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST 274 FT EAST OF THE CENTER OF WEBSTERVILLE RD/CHURCHILL RD INTERSECTION	X			
WB	MM 1.395, LT	F	DI-1	72	12			6.00								2		X						INSTALL NEW SIGN ON 2-POSTS 465 FT EAST OF THE CENTER OF WEBSTERVILLE RD/CHURCHILL RD INTERSECTION (OR JUST 205 FT WEST OF GREGOIRE ST)			9	
		F	DI-1	72	12			6.00																INSTALL NEW SIGN BENEATH WEBSTERVILLE DESTINATION SIGN ON THE SAME POSTS			9	
		F	DI-1	72	12			6.00																INSTALL NEW SIGN BENEATH THE GRANITEVILLE DESTINATION SIGN ON THE SAME POSTS			9	

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

SHEET SUBTOTALS

			EA	EA	EA	EA	EA	EA		FT	FT	FT		LB	LB	LB	LB
			1	1	3	1	2			90							
SF	SF		EA	EA	EA	EA	EA	EA	FT	EA	LB						
56.52			5			3		6	90								

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARRE TOWN (4) TSS SHEET 5

PLOT DATE: 13-SEP-2012 15:48
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 31 OF 64