STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7 – BARRE TOWN 4 (WEBSTERVILLE RD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
EB	MM 2.025, RT	A/B	D3-1	24	6		TEJA RD			X				X												RETAIN TEJA RD STREET NAME SIGN AND POST			
		C/D	D3-1	42	6		Websterville Rd			X																RETAIN SIGN			
		A B	W1-8 R W1-8 L	18 18	24 24		B-B						X X													REMOVE 2-SIGNS			
EB	MM 2.035, RT	A B	W1-8 R W1-8 L	18 18	24 24		B-B	3.00 3.00					X X		X	1		X								INSTALL NEW CHEVRONS BACK-TO-BACK ON A SIGN BRACKET ON A SINGLE POST 63 FT WEST OF POLE# 110369/32/141	X X		
EB	MM 2.047, RT	A B	W1-8 R W1-8 L	18 18	24 24		B-B						X X		X											REMOVE 2-SIGNS AND POST			
EB	MM 2.050, RT	A B	W1-8 R W1-8 L	18 18	24 24		B-B	3.00 3.00								1		X								INSTALL NEW CHEVRONS BACK-TO-BACK AT ON A SIGN BRACKET ON A SINGLE POST 63 FT WEST OF THE CENTER OF TEJA RD LOCATED NEAR POLE# 110369/32/141	X X		
EB	MM 2.062, RT	D	R1-2	36	36		YIELD	3.89					X		X	1		X								INSTALL NEW SIGN AND POST AT TEJA RD LOCATED NEAR POLE# 110369/32/141	X		
EB	MM 2.066, RT	A B	W1-8 R W1-8 L	18	24		B-B	3.00 3.00								1		X								INSTALL NEW CHEVRONS BACK-TO -BACK AT SAME LOCATION (21 FT EAST OF THE CENTER OF TEJA RD LOCATED NEAR POLE # 110369/32/141)	X X		
EB	MM 2.109, LT	F	W1-1R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 10 FT EAST OF POLE# 34/143	X		
EB	MM 2.121, RT	A	W1-1R	30	30			6.25					X		X	1		X								INSTALL NEW SIGN AND POST 63 FT EAST OF AND ACROSS FROM POLE# 34/143	X		
EB	MM 2.141, RT	A/B	D3-1	24	6		CHURCH ST			X				X												RETAIN SIGN AND POST INSTALL STOP SIGN BENEATH CHURCH STREET SIGN			
		D	R1-1	30	30		STOP	6.25					X													REMOVE SIGN AND INSTALL NEW SIGN ON THE SAME POST BELOW THE EXISTING STREET NAME SIGN (CHURCH ST)	X		
EB	MM 2.169, RT TO MM 2.226, RT	A B		6	8		(14) TYPE II - 6" X 8" WHITE DELINEATORS	4.67					X		X	7	X									REMOVE THE 6 DELINEATOR POSTS AND REFLECTORS AND INSTALL 7 NEW DELINEATOR POSTS WITH BACK-TO-BACK DELINEATORS AT 50 FT SPACING GOING EAST WITH THE FIRST SET INSTALLED 48 FT WEST OF AND OPPOSITE POLE # 145-1/37/40711		7	
WB	MM 2.176, LT	E	W1-6	48	24			8.00								2		X								INSTALL SIGN AND POSTS 10 FT WEST OF POLE # 145-1/37/40711	X		
							SHEET SUBTOTALS	SF 53.31	SF	EA 3	EA	EA	EA 10	EA 2	EA 5	EA 15	FT 56	FT 120	FT	EA	LB	LB	LB	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARRE TOWN (4) TSS SHEET 7
PLOT DATE: 13-SEP-2012 15:48
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 33 OF 64