STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 – BARRE TOWN 5
(GRANITEVILLE RD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHS = STANDARD HIGHWAY SIGN BOOK)	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
							CHURCH HILL RD																					
SB	MM 0.011, LT	F	RI-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT THE SAME LOCATION (INTERSECTION WITH GRANITEVILLE RD)	X		
NB	MM 0.021, RT	A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 110 FT FROM THE CENTER OF GRANITEVILLE RD		7	
SB	MM 0.038, LT	F	DI-1	72	12		← Upper Graniteville	6.00								2		X								INSTALL NEW SIGN ON 2-POSTS 53 FT SOUTH OF POLE 79268/57/2		11	
		F	DI-1	72	12		Graniteville →	6.00																		INSTALL NEW SIGN BENEATH THE UPPER GRANITEVILLE DESTINATION SIGN ON THE SAME POSTS		11	
		F	DI-1	72	12		South Barre →	6.00																		INSTALL NEW SIGN BENEATH THE GRANITEVILLE DESTINATION SIGN ON THE SAME POSTS		11	
NB	MM 0.043, RT	A	R2-1	24	30		SPEED LIMIT 25	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 26 FT SOUTH OF AND ACROSS FROM POLE# 79268/57/2	X		
SB	MM 0.069, LT	F	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS AT POLE# 79267/56	X		
NB	MM 0.403, RT	A	R2-1	24	30		SPEED LIMIT 25	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 174 FT NORTH OF POLE# 79252/42/17	X		
SB	MM 0.466, LT	A	R2-1	24	36		SPEED LIMIT 25	5.00					X		X	1		X								INSTALL NEW SIGN AND POST IN FRONT OF POLE# 8-2/90/79249/37	X		
NB	MM 0.467, RT	A	S1-1	36	36	F-Y-G		9.00					X		X	2		X								INSTALL NEW SIGN ON 2-POSTS 10 FT SOUTH OF POLE# 8-2/90/79249/37	X		
		A	W16-9P	24	12	F-Y-G	AHEAD	2.00					X													INSTALL NEW SIGN BENEATH SCHOOL SYMBOL WARNING SIGN ON THE SAME POSTS	X		
NB	MM 0.558, RT	A	S1-1	36	36	F-Y-G				X				X												RETAIN SIGN AND POST AT CROSSWALK ACROSS FROM POLE# 33/85/79244			
		A	W16-7P	24	12	F-Y-G				X																RETAIN SIGN			
SB	MM 0.561, LT	F	S1-1	36	36	F-Y-G				X				X												RETAIN SIGN AND POST AT CROSSWALK NEAR POLE# 33/85/79244			
		F	W16-7P	24	12	F-Y-G				X																RETAIN SIGN			
										EA 4	EA	EA	EA 7	EA 2	EA 6		FT	FT 165	FT					LB	LB	LB	LB				
							SHEET SUBTOTALS	SF 64.25	SF	EA 11				EA 8		EA 11	FT 165			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARRE TOWN (5) TSS SHEET 1
PLOT DATE: 13-SEP-2012 15:48
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 36 OF 64