STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4 – BARRE TOWN 5
(GRANITEVILLE RD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHS = STANDARD HIGHWAY SIGN BOOK)	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
NB	MM 1.233, RT	A	M4-5	24	12		TO B-B TO						X		X											REMOVE 2-SIGNS AND POST			
		B	M4-5	24	12								X															
		A	MI-6	30	24		110 B-B 110						X													REMOVE 2-SIGNS			
		B	MI-6	30	24								X															
		A	M6-4	21	15		B-B						X													REMOVE 2-SIGNS			
		B	M6-4	21	15								X															
		A	M4-5	24	12		TO	2.00								1		X								INSTALL NEW SIGN AND POST 79 FT SOUTH OF AND ACROSS FROM POLE# 6-02/12074I			E-136B
		A	MI-5	30	24		VERMONT 110	5.00																		INSTALL NEW SIGN BENEATH TO AUXILIARY SIGN ON THE SAME POST			E-136B
		A	M6-1R	21	15			2.19																		INSTALL NEW SIGN BENEATH VT 110 ROUTE MARKER ON THE SAME POST			E-136B
		A	M4-5	24	12		TO	2.00								1		X								INSTALL NEW SIGN AND POST DIRECTLY TO THE RIGHT OF PREVIOUSLY INSTALLED ROUTEMARKER ASSEMBLY 79 FT SOUTH OF AND ACROSS FROM POLE# 6-02/12074I	X		
		A	MI-4	30	24		302	5.00																		INSTALL NEW BENEATH TO AUXILIARY SIGN ON THE SAME POST	X		
		A	M6-1R	21	15			2.19																		INSTALL NEW SIGN BENEATH THE US 302 ROUTE MARKER ON THE SAME POST	X		
							GRANITEVILLE RD																							
NB	MM - 0.008, RT	D	RI-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT THE SAME LOCATION, 76 FT SOUTH OF POLE# 79442/3/8-10/2	X		
SB	MM 0.000, LT	G	WI-7	48	24			8.00					X		X X	2		X								INSTALL NEW SIGN AND POSTS ON THE RIGHTHAND SIDE OF THE GRANITEVILLE RD INTERSECTION , 116 FT SOUTH OF AND ACROSS FROM POLE# 79442/3/8-10/2	X		
NB	MM 0.005, RT	D	RI-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT THE SAME LOCATION (LEFTHAND SIDE OF GRANITEVILLE RD)	X		
																EA 9	EA	EA	EA	EA	EA 5		FT 90	FT	FT		LB	LB	LB	LB			
							SHEET SUBTOTALS	SF 38.88	SF					EA 9		EA 5	EA 6		FT 90		EA		LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARRE TOWN (5) TSS SHEET 4

PLOT DATE: 13-SEP-2012 15:48
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 39 OF 64