STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5 – BARRE TOWN 5 (GRANITEVILLE RD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.028, RT	A	MI-1	24	24		INTERSTATE 89						X		X											REMOVE SIGN AND POST			
		A	M6-3	21	15		↑						X													REMOVE SIGN			
NB	MM 0.035, RT	A	M4-5	24	12		TO						X		X											REMOVE SIGN AND POST			
		A	MI-5	24	24		VERMONT 14						X													REMOVE SIGN			
		A	M6-3	21	15		↑						X													REMOVE SIGN			
NB	MM 0.035, RT	A	TOWN SIGN	24	24		TRUCK ROUTE ↗						X		X											REMOVE SIGN AND POST			
NB	MM 0.035, RT	A	M4-5	24	12		TO	2.00								2			X						3A	INSTALL 10 NEW SIGNS ON 2-POSTS 5 FT DIRECTLY SOUTH OF POLE #79440/38 #10-8/99 IN THE GRASSED ISLAND BETWEEN THE GRANITEVILLE ROAD AND THE SLIP RAMP		7	E-136B
		A	MI-5	24	24		VERMONT 14	4.00																		INSTALL NEW "TO", VT 14 AND UP LEFT ARROW SIGNS ON THE LEFT SIDE OF THE NEW ASSEMBLY			E-136B
		A	M6-2	21	15		↖	2.19																		INSTALL NEW "TO", VT 14 AND UP LEFT ARROW SIGNS ON THE LEFT SIDE OF THE NEW ASSEMBLY (5 FT IN FRONT OF POLE # 79440/38/10-8/99)			
NB	MM 0.0352, RT	A	M4-5	24	12		TO	2.00																		INSTALL NEW "TO", I-89 AND UP LEFT ARROW SIGNS IN THE MIDDLE OF THE NEW ASSEMBLY	X		
		A	MI-1	24	24		INTERSTATE 89	4.00																		INSTALL NEW "TO", I-89 AND UP LEFT ARROW SIGNS IN THE MIDDLE OF THE NEW ASSEMBLY	X		
		A	3M6-2	21	15		↖	2.19																		INSTALL NEW "TO", I-89 AND UP LEFT ARROW SIGNS IN THE MIDDLE OF THE NEW ASSEMBLY	X		
NB	MM 0.035, RT	A	RI4-1	24	18		TRUCK ROUTE	3.00																		INSTALL NEW TRUCK ROUTE, TO, VT 14 AND UP RIGHT ARROW SIGNS ON THE RIGHT SIDE OF THE NEW ASSEMBLY	X		
		A	M4-5	24	12		TO	2.00																		INSTALL NEW TRUCK ROUTE, TO, VT 14 AND UP RIGHT ARROW SIGNS ON THE RIGHT SIDE OF THE NEW ASSEMBLY			E-136B
		A	MI-5	24	24		VERMONT 14	4.00																		INSTALL NEW TRUCK ROUTE, TO, VT 14 AND UP RIGHT ARROW SIGNS ON THE RIGHT SIDE OF THE NEW ASSEMBLY			E-136B
		A	M6-2	21	15		↗	2.19																		INSTALL NEW TRUCK ROUTE, TO, VT 14 AND UP RIGHT ARROW SIGNS ON THE RIGHT SIDE OF THE NEW ASSEMBLY			E-136B
										EA	EA	EA	EA	EA	EA		FT	FT	FT		LB	LB	LB	LB					
													6		3				30											
			SHEET SUBTOTALS					SF 27.57	SF	EA 6				EA 3		EA 2	FT 30			EA	LB									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARRE TOWN (5) TSS SHEET 5

PLOT DATE: 13-SEP-2012 15:48
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 40 OF 64