
















TRAFFIC SIGN SUMMARY SHEET 7 - BARRE TOWN 5

(GRANITEVILLE RD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL		
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		FOUNDATION			lb/ft						DETAIL IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
																	1.75	2.00	2.50	3.00	3.50	4.00	5.00					
SB	MM 0.329, LT	F	R2-1	24	30			5.00					X		X	1		X						INSTALL NEW SIGN AND POST 58 FT NORTH OF POLE# 2/79340/8-6/2	X			
NB	MM 0.337, RT	A	DI-1	72	12			6.00								2		X						INSTALL NEW SIGN ON 2- POSTS 15 FT NORTH OF AND ACROSS FROM POLE# 2/79340/8-6/2			II	
		A	DI-1	72	12			6.00																INSTALL NEW SIGN BENEATH SOUTH BARRE DESTINATION SIGN ON THE SAME POST			II	
SB	MM 0.435, LT	G	WI4-2A	30	30						X	X	X	X										SALVAGE SIGN AND POST. INSTALL SIGN 50 FT EAST OF SIGN IS AT THE TOP OF POST (PEARL ST)				
SB	MM 0.435, LT	G	R2-1	24	30						X		X											SALVAGE SIGN (PEARL ST)				
SB	MM 0.435 LT + 50 FT, LT	G	R2-1	24	30								X			1		X						INSTALL SALVAGED SIGN AND NEW POST 50 FT EAST OF NO OUTLET SIGN ASSEMBLY (PEARL ST)				
NB	MM 0.440, RT	D	RI-1	30	30			6.25					X		X	1		X						REMOVE STOP SIGN AND INSTALL NEW STOP SIGN ON NEW POST (SIGN IS FOR DODGE AVE)	X			
		C	D3-1	30	6						X	X	X											SALVAGE SIGN AND INSTALL ON TOP OF STOP SIGN ON THE SAME POST				
NB	MM 0.450, RT	C	R2-1	24	30					X					X									RETAIN SIGN AND POST				
NB	MM 0.450, RT	C	WI4-2A	30	30						X		X											SALVAGE SIGN (DODGE AVE)				
		C	TOWN SIGN	24	30						X	X	X											SALVAGE SIGN INSTALL SIGN BENEATH SPEED LIMIT SIGN ON THE SAME (DODGE AVE)				
NB	MM 0.450, RT + 50 FT, RT	C	WI4-2A	30	30								X			1		X						INSTALL SALVAGED SIGN AND NEW POST 50 FT WEST OF THE 25 MPH SPEED LIMIT SIGN ASSEMBLY (PEARL ST)				
NB	MM 0.524, RT	D	R2-1	30	30			6.25					X		X	1		X						REMOVE STOP SIGN AND INSTALL NEW STOP SIGN ON NEW POST (SIGN IS FOR MCLEOD HILL RD)	X			
		C	D3-1	36	6						X	X	X											SALVAGE SIGN AND INSTALL ON TOP OF STOP SIGN ON THE SAME POST				
NB	MM 0.553, RT	A	WI1A-2	30	30								X		X									REMOVE SIGN AND POST				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

SHEET SUBTOTALS

EA	EA	EA	EA	EA	EA	FT	FT	FT	LB	LB	LB	LB
1	6	6	10	2	4	105						
SF	SF	EA	EA	EA	EA	FT	EA	EA	EA	EA	EA	EA
29.50		23	6	7		105						

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARRE TOWN (5) TSS SHEET 7

PLOT DATE: 13-SEP-2012 15:48
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 42 OF 64