STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8 – BARRE TOWN 5 (GRANITEVILLE RD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
SB	MM 0.566, LT	F	R2-1	24	30		SPEED LIMIT 25	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 79 FT NORTH OF POLE# 13/79289/13	X		
NB	MM 0.566, RT	A	R2-1	24	30		SPEED LIMIT 25	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 79 FT NORTH OF AND ACROSS FROM POLE# 13/79289/13	X		
		A		6	10		0630 1202 0100				X	X	X													SALVAGE SIGN AND INSTALL BENEATH SPEED LIMIT 25 SIGN ON THE SAME POST			
NB	MM 0.604, RT	A	W11-2	30	30	F-Y-G		6.25								1		X								INSTALL NEW SIGN AND POST 21FT SOUTH OF AND ACROSS FROM POLE# 14/14/79288/14	X		
		A	W16-9P	24	12	F-Y-G	AHEAD	2.00																		INSTALL NEW SIGN BENEATH PEDESTRIAN SYMBOL WARNING SIGN AT THE CORRECT SIGN HEIGHT	X		
SB	MM0.775, LT	F	D1-1	72	12		Upper Graniteville	6.00								2		X								INSTALL NEW SIGN ON 2-POSTS 10 FT NORTH OF POLE # 23/23/79276		11	
		F	D1-1	72	12		Websterville	6.00																		INSTALL NEW SIGN BENEATH UPPER GRANITEVILLE DESTINATION SIGN ON THE SAME POSTS		9	
		F	D1-1	72	12		East Barre	6.00																		INSTALL NEW SIGN BENEATH WEBSTERVILLE DESTINATION SIGN ON THE SAME POSTS		11	
NB	MM 0.777, RT	A	R2-1	24	30		SPEED LIMIT 25	5.00					X		X	1		X								INSTALL NEW SIGN AND POST ACROSS FROM POLE# 23/23/79276	X		
										EA	EA 1	EA 1	EA 4	EA	EA 3		FT	FT 90	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 41.25	SF	EA 6				EA 3		EA 6	FT 90			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARRE TOWN (5) TSS SHEET 8

PLOT DATE: 13-SEP-2012 15:48
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 43 OF 64