STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 10 – BARRE TOWN 5 (GRANITEVILLE RD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
NB	MM 0.892, RT	A	M4-5	24	12		TO	2.00					X		X	2			X						3A	INSTALL 9 NEW SIGNS ON 2-POSTS 5 FT DIRECTLY SOUTH OF POLE#82174/28/28	X		
		A	MI-1	24	24		INTERSTATE 89	4.00					X														INSTALL NEW "TO", I-89 AND UP ARROW SIGNS ON THE LEFT SIDE OF THE NEW ASSEMBLY	X		
		A	M6-3	21	15		↑	2.19					X														INSTALL NEW "TO", I-89 AND UP ARROW SIGNS ON THE LEFT SIDE OF THE NEW ASSEMBLY	X		
		A	M4-5	24	12		TO	2.00					X														INSTALL NEW "TO", VT 110 AND HORIZONTAL RIGHT ARROW SIGNS IN THE MIDDLE OF THE NEW ASSEMBLY			E-136B
		A	MI-5	30	24		VERMONT 110	5.00					X														INSTALL NEW "TO", VT 110 AND HORIZONTAL RIGHT ARROW SIGNS IN THE MIDDLE OF THE NEW ASSEMBLY			E-136B
		A	M6-1	21	15		→	2.19					X														REMOVE SIGNS AND POST AND INSTALL NEW "TO", VT 110 AND HORIZONTAL RIGHT ARROW SIGNS IN THE MIDDLE OF THE NEW ASSEMBLY			E-136B
		A	M4-5	24	12		TO	2.00					X														REMOVE SIGNS AND POST AND INSTALL NEW "TO", US 302 AND HORIZONTAL RIGHT ARROW SIGNS ON THE RIGHT SIDE OF THE NEW ASSEMBLY	X		
		A	MI-4	30	24		302	5.00					X														REMOVE SIGNS AND POST AND INSTALL NEW "TO", US 302 AND HORIZONTAL RIGHT ARROW SIGNS ON THE RIGHT SIDE OF THE NEW ASSEMBLY	X		
		A	M6-1	21	15		→	2.19					X														REMOVE SIGNS AND POST AND INSTALL NEW "TO", US 302 AND HORIZONTAL RIGHT ARROW SIGNS ON THE RIGHT SIDE OF THE NEW ASSEMBLY	X		
		A	TOWN SIGN	48	24		TO 89 BARRE CITY ↑						X														REMOVE SIGN			
SB	MM0.896, LT	F	R2-1	24	30		SPEED LIMIT 25	5.00					X		X	1		X									INSTALL NEW SIGN AND POST 21FT SOUTH OF AND ACROSS FROM POLE# 82174/28/28	X		
NB	MM 0.936, RT	A	TOWN SIGN	30	30		PRESBYTERIAN CHURCH ½ MILE						X		X												REMOVE SIGN AND POST RETURN TO TOWN			
		A	DI-1	72	12		↑ South Barre	6.00								2		X									INSTALL NEW SIGN ON 2-POSTS 15 FT SOUTH OF POLE# 8-6/30/30/82/69		II	
		A	DI-1	72	12		Websterville →	6.00																			INSTALL NEW SIGN BENEATH SOUTH BARRE DESTINATION SIGN ON THE SAME POSTS		9	
		A	DI-1	72	12		East Barre →	6.00																			INSTALL NEW SIGN BENEATH THE WEBSTERVILLE DESTINATION SIGN ON THE SAME POSTS		II	
										EA	EA	EA	EA 12	EA	EA 3		FT	FT 45	FT 30		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 49.57	SF	EA 12				EA 3		EA 5	FT 75			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARRE TOWN (5) TSS SHEET 10
PLOT DATE: 13-SEP-2012 15:48
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 45 OF 64