

TRAFFIC SIGN SUMMARY SHEET 12- BARRE TOWN 5 (GRANITEVILLE RD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS <small>SHS = STANDARD HIGHWAY SIGN BOOK</small>	SIGN DETAIL			
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		FOUNDATION			lb/ft						DETAIL IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER	
																	1.75	2.00	2.50	3.00	3.50	4.00	5.00						
SB	MM 1.529, LT	F	M4-5	24	12																			REMOVE SIGN					
		F	MI-4	30	24																				REMOVE SIGN				
		F	M6-1	21	15																				REMOVE SIGN				
SB	MM 1.529, LT	G		36	24						X	X	X	X											SALVAGE SIGN AND INSTALL AT TOP EDGE OF SIGN TO TOP OF RETAINED POST				
NB	MM 1.530, RT	D	RI-1	30	30			6.25					X	X	I		X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT THE SAME LOCATION (DONAHUE RD)	X			
SB	MM 1.560, LT	F	R2-1	24	30			5.00					X	X	I		X								INSTALL NEW SIGN AND POST 68 FT NORTH OF AND ACROSS FROM POLE# 75212/8/8	X			
NB	MM 1.656, RT	A	R2-1	24	30								X												REMOVE SIGN				
NB	MM 1.656, RT	A		24	30						X	X	X	X											SALVAGE SIGN AND INSTALL AT TOP EDGE OF SIGN TO TOP OF RETAINED POST				
NB	MM 1.673, RT	A	VR-017	24	30			5.00					X	X	I		X								INSTALL NEW SIGN AND POST 69 FT SOUTH OF POLE# 12/75/2/8/12		7		
		A	R2-1	24	30			5.00																	INSTALL NEW SIGN BENEATH LEGAL LOAD LIMIT SIGN ON THE SAME POST	X			
GRANITEVILLE ROAD SLIP RAMP																													
NB	STA 3+70 FT RT FROM POLE# 79432/13/8/100	B	R5-1	30	30			6.25					X	X	I		X								INSTALL NEW SIGN AND POST AT THE SAME LOCATION ON THE SLIP RAMP BACK-TO-BACK WITH YIELD SIGN 370 FT NORTH OF POLE# 79432/13/8/100	X			
		A	RI-2	36	36			3.89					X												INSTALL NEW SIGN TO THE BACK SIDE OF THE DO NOT ENTER SIGN ON THE SLIP RAMP 370 FT NORTH OF POLE# 79432/13/8/100	X			
SB	STA 3+33 FT LT FROM POLE# 79432/13/8/100	F	R5-1	30	30			6.25					X	X	I		X								INSTALL NEW SIGN AND POST AT THE SAME LOCATION ON THE SLIP RAMP 37 FT SOUTH OF AND ACROSS FROM THE PREVIOUSLY INSTALLED YIELD SIGN ASSEMBLY, 333 FT NORTH OF POLE# 79432/13/8/100	X			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

SHEET SUBTOTALS

			EA	EA	EA	EA	EA	EA		FT	FT	FT		LB	LB	LB	LB
			2	2	12	2	5			75							
SF	SF		EA	EA	EA				FT		EA		LB				
37.64			16	7	5			75									

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn PLOT DATE: 13-SEP-2012 15:49
PROJECT LEADER: JLS DRAWN BY: ITS
DESIGNED BY: NLA CHECKED BY: JLS
BARRE TOWN (5) TSS SHEET 12 SHEET 47 OF 64