STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - LYNDON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							CENTER STREET																						
NB	MM 0.297, RT	A	R2-5A	24	30		REDUCED SPEED AHEAD						X		X											REMOVE SIGN AND POST			
		A	W3-5	36	36		SPEED LIMIT 25	9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 69 FT NORTH OF AND ACROSS FROM POLE# 50/12	X		
SB	MM 0.306, LT	F	VR-004A	24	30								X		X											REMOVE SIGN AND POST			
NB	MM 0.338, RT	A	R2-1	24	30		SPEED LIMIT 25	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 11FT SOUTH OF AND ACROSS FROM POLE# 48/14	X		
SB	MM 0.338, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 11FT SOUTH OF POLE# 48/14 ACROSS FROM THE SPEED LIMIT S5 SIGN ASSEMBLY	X		
NB	MM 0.403, RT	A	W1-3 R	30	30								X		X											REMOVE SIGN AND POST			
		A	W13-1P	18	18		15 M.P.H.						X													REMOVE SIGN			
NB	MM 0.427, RT	A	W1-1 R	30	30								X		X											REMOVE SIGN AND POST			
		A	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 16 FT SOUTH OF AND ACROSS FROM POLE# 18/3/45	X		
NB	MM 0.492, RT	A	W1-1 R	30	30								X		X											REMOVE SIGN AND POST	X		
		A	D1-1	72	12		Lyndon Center →	6.00								2		X								INSTALL NEW SIGN ON 2-POSTS 327 FT NORTH OF AND ACROSS FROM POLE# 18/3/45		12	
		A	D1-1	72	12		Lyndon St College →	6.00																		INSTALL NEW SIGN BENEATH LYNDON CENTER DESTINATION SIGN ON THE SAME POSTS		12	
NB	MM 0.540, RT	A	R1-1	30	30		STOP	6.25								1		X								INSTALL NEW SIGN AND POST ADJACENT TO POLE# 41A	X		
SB	MM 0.549, LT	G	W1-7	48	24			8.00					X		X	2		X								INSTALL NEW SIGN ON 2-POSTS 48 FT NORTH OF AND ACROSS FROM POLE# 41A	X		
SB	MM 0.575, LT	F	W1-1 L	30	30								X		X											REMOVE SIGN AND POST			
										EA	EA	EA	EA 10	EA	EA 9		FT	FT 165	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 54.25	SF	EA 10				EA 9		EA 11	FT 165			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
LYNDON TRAFFIC SIGN SUMMARY SHEET 1
PLOT DATE: 13-SEP-2012 15:49
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 49 OF 64