STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - LYNDON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.584, RT	A	R2-1	24	30		SPEED LIMIT 25	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 16 FT NORTH OF AND ACROSS FROM POLE# 3/39	X		
SB	MM 0.598, LT	F	W1-2 L	30	30								X		X											REMOVE SIGN AND POST	X		
		F	W13-1	18	18		15 M.P.H.						X													REMOVE SIGN	X		
		F	W1-1MbL	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 37 FT SOUTH OF POLE# 3/38/4		12	
		F	W16-8	36	8		Back Center Rd	2.00																		INSTALL NEW SIGN BENEATH MODIFIED TURN LEFT WARNING SIGN ON THE SAME POST AT THE CORRECT SIGN HEIGHT		12	
NB	MM 0.618, RT	A	W11A-2	30	30								X		X											REMOVE SIGN AND POST			
		A	VR-017	24	30		LEGAL LOAD LIMIT 16,000 POUNDS						X													REMOVE SIGN			
		A	W11-2	30	30	F-Y-G		6.25								1		X								INSTALL NEW SIGN AND POST 53 FT NORTH OF AND ACROSS FROM POLE# 3/38/4 NEAR END OF CROSSWALK	X		
		A	W16-7P	24	12	F-Y-G		2.00																		INSTALL NEW SIGN BENEATH PEDESTRIAN SYMBOL WARNING SIGN ON THE SAME POST AT THE CORRECT SIGN HEIGHT	X		
SB	MM 0.616, LT	H	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT THE SAME LOCATION (INTERSECTION WITH COLLEGE RD)	X		
SB	MM 0.011, LT	F	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT THE SAME LOCATION NEXT TO POLE# VS55/3/37-1 (INTERSECTION WITH MATTY HOUSE CIR)	X		
SB	MM 0.640, LT	F	W11A-2	30	30								X		X											REMOVE SIGN AND POST			
		F	W11-2	30	30	F-Y-G		6.25								1		X								INSTALL NEW SIGN AND POST 53 FT NORTH OF POLE# 3/37	X		
		F	W16-7P	24	12	F-Y-G		2.00																		INSTALL NEW SIGN BENEATH PEDESTRIAN SYMBOL WARNING SIGN ON THE SAME POST AT THE CORRECT SIGN HEIGHT	X		
NB	MM 0.011, LT	A	VR-017	24	30		LEGAL LOAD LIMIT 16,000 POUNDS	5.00																		INSTALL NEW SIGN ON THE POST CLOSEST TO THE ROADWAY OF THE EXISTING LOW CLEARANCE BRIDGE AHEAD SIGN ASSEMBLY LOCATED 79 FT SOUTH OF AND ACROSS FROM POLE# 6/36		7	
										EA	EA	EA	EA 8	EA	EA 6			FT 90				LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 47.25	SF	EA 8				EA 6		EA 6		FT 90		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
LYNDON TRAFFIC SIGN SUMMARY SHEET 2

PLOT DATE: 13-SEP-2012 15:49
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 50 OF 64