STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 – WESTFIELD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.0045, RT	C/D	D3-1	42	12		Buck Hill Rd	3.50					X		X	1		X								INSTALL NEW SIGN ABOVE STOP SIGN ON THE SAME POST		10	
		A	R1-1	30	30		STOP	6.25																		INSTALL NEW AND POST 25 FT SOUTH OF THE CENTER OF THE VT 100 INTERSECTION WITH BUCK HILL ROAD	X		
NB	MM 0.006, RT	D	R1-1	30	30		STOP						X		X											REMOVE SIGN AND POST	X		
SB	MM 0.014, LT	F	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 73 FT SOUTH OF THE CENTER OF THE VT 100 INTERSECTION)		7	
SB	MM 0.329, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST 173 FT SOUTH OF THE CENTER OF THE VT 100 INTERSECTION	X		
NB	MM 0.053, RT	A	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 250 FT SOUTH OF THE CENTER OF THE VT 100 INTERSECTION	X		
NB	MM 0.507, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST 100 FT NORTH OF THE CENTER OF BALANCE ROCK RD	X		
SB	MM 0.522, LT	E/F	D3-1	48	12		Balance Rock Rd	4.00					X		X											INSTALL NEW SIGN ABOVE STOP SIGN ON THE SAME POST		10	
SB	MM 0.537, LT	F	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT THE SAME LOCATION (BALANCE ROCK RD)	X		
SB	MM 0.545, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST 100 FT SOUTH OF AND ACROSS FROM THE CENTER OF BALANCE ROCK RD	X		
NB	MM 0.899, RT	A	W1-2L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 30 FT NORTHEAST OF MAIL BOX 906, 900 FT NORTHEAST OF THE CENTER OF TAFT BROOK RD	X		
SB	MM 0.945, LT	F	TOWN SIGN	30	30		SLOW						X		X											REMOVE SIGN AND POST			
		F	TOWN SIGN	30	30		CAUTION BLIND INTERSECTION						X													REMOVE SIGN			
SB	MM 0.945, LT	F	W2-1	30	30			6.25								2		X								INSTALL NEW SIGN ON 2-POSTS 660 FT NORTH OF THE CENTER OF TAFT BROOK ROAD	X		
		F	W7-6	30	30		HILL BLOCKS VIEW	6.25																		INSTALL NEW SIGN BENEATH THE INTERSECTION WARNING SIGN ON THE SAME POST AT THE CORRECT SIGN HEIGHT	X		
										EA	EA	EA	EA 7	EA	EA 6			FT	FT 165	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 67.75	SF	EA 7				EA 6		EA 11		FT 165		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
WESTFIELD TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 13-SEP-2012 15:50
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 57 OF 64