STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 2 – WESTFIELD

| DIRECTION | MILEMARKER, STATION, OR SIGN NUMBER | LOCATION | MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE | SIGN DIMENSIONS WIDTH | SIGN DIMENSIONS HEIGHT | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXISTING POST RETAIN | EXISTING POST REMOVE | NO. OF NEW POSTS | SQUARE STEEL (in) 1.75 lb/ft 1.88 | SQUARE STEEL (in) 2.00 lb/ft 2.42 | SQUARE STEEL (in) 2.50 lb/ft 3.35 | TUBULAR STEEL O/(in) FOUNDATION | TUBULAR STEEL O/(in) 3.00 lb/ft 7.60 | TUBULAR STEEL O/(in) 3.50 lb/ft 9.00 | TUBULAR STEEL O/(in) 4.00 lb/ft 10.80 | TUBULAR STEEL O/(in) 5.00 lb/ft 14.60 | SIGN FRAME REQUIRED | REMARKS SHS = STANDARD HIGHWAY SIGN BOOK | SIGN DETAIL DETAIL IN SHS | SIGN DETAIL DETAIL ON SHEET NUMBER | SIGN DETAIL STANDARD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| SB | MM 1.085, LT | E/F | D3-1 | 48 | 12 | | Taft Brook Rd | 4.00 | | | | | | | | 1 | | X | | | | | | | | INSTALL NEW STREET NAME SIGN ON A NEW POST AT TAFT BROOK RD | | 10 | |
| SB | MM 1.881, LT | F | W1-2L | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST 625 FT SOUTHWEST OF BELISLE FARM (MAIL BOX 1715) | X | | |
| NB | MM 1.858, RT | A | R2-1 | 24 | 30 | | SPEED LIMIT 35 | 5.00 | | | | | | | | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST 500 FT SOUTHWEST OF BELISLE FARM (MAIL BOX 1715) | X | | |
| SB | MM 1.919, LT | F | W1-6L | 48 | 24 | | | 8.00 | | | | | | | | 2 | | X | | | | | | | | INSTALL NEW SIGN AND POSTS 823 FT SOUTHWEST OF BELISLE FARM (MAIL BOX 1715). INSTALL IN LINE WITH THE SOUTHWESTBOUND DRIVERS' LINE OF SIGHT | X | | |
| SB | MM 2.059, LT | F | W-054A | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST 250 FT NORTHEAST OF MASSINO RESIDENCE (MAIL BOX 2024) | | 10 | |
| SB | MM 2.226, LT | F | TOWN SIGN | 18 | 24 | | | | | | | | X | | X | | | | | | | | | | | REMOVE SIGN AND POST | | | |
| NB | MM 2.438, RT | A | R2-1 | 24 | 30 | | SPEED LIMIT 35 | 5.00 | | | | | | | | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST 125 FT NORTHEAST OF THE CENTER OF THE NORTH LEG OF TRUMPASS RD | X | | |
| NB | MM 2.454, RT | D | R1-1 | 30 | 30 | | STOP | 6.25 | | | | | X | | X | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST AT NORTH LEG OF TRUMPASS RD ON THE RIGHT SIDE | X | | |
| NB | MM 2.497, RT | A/B | D3-1 | 42 | 12 | | Trumpass Rd | 3.50 | | | | | | | | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST IN THE MIDDLE OF THE TRIANGLE FORMED BY THE TWO LEGS OF TRUMPASS RD | | 10 | |
| | | C/D | D3-1 | 42 | 12 | | Buck Hill Rd | 3.50 | | | | | | | | | | | | | | | | | | INSTALL NEW SIGN BENEATH TRUMPASS SIGN ON THE SAME POST | | 10 | |
| NB | MM 2.499, RT | D | R1-1 | 30 | 30 | | STOP | 6.25 | | | | | X | | X | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST AT SOUTH LEG OF TRUMPASS RD ON THE RIGHT SIDE | X | | |
| NB | MM 2.520, RT | A/B | D3-1 | 36 | 6 | | Trumpass Rd | | | | | | X | | X | | | | | | | | | | | REMOVE SIGN AND POST | | | |
| SB | MM 2.535, LT | F | R2-1 | 24 | 30 | | SPEED LIMIT 35 | 5.00 | | | | | | | | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST 125 FT SOUTHWEST OF THE CENTER OF THE SOUTH LEG OF TRUMPASS RD | X | | |
| NB | MM 2.566, RT | A | TOWN SIGN | 18 | 24 | | | | | | | | X | | X | | | | | | | | | | | REMOVE SIGN AND POST | | | |
| | | A | W2-2R | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST 312 FT SOUTH OF THE MOST SOUTHERLY LEG OF TRUMPASS RD INTERSECTION | X | | |
| | | A | W16-8P | 30 | 8 | | Trumpass Rd | 1.67 | | | | | | | | | | | | | | | | | | INSTALL NEW SIGN BENEATH THE INTERSECTION SIDE ROAD WARNING SIGN AT THE CORRECT SIGN HEIGHT | | 10 | |
| | | | | | | | | | | EA | EA | EA | EA 5 | EA | EA 5 | | FT | FT 180 | FT | | | | | LB | LB | LB | LB | | | | | |
| | | | | | | | **SHEET SUBTOTALS** | SF 66.92 | SF | EA 5 | | | | EA 5 | | EA 12 | FT 180 | | | EA | LB | | | | | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(4)

FILE NAME: 10k016_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 13-SEP-2012 15:50
DRAWN BY: ITS
CHECKED BY: JLS
WESTFIELD TRAFFIC SIGN SUMMARY SHEET 2 SHEET 58 OF 64