

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES											TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
										ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
										500	500		CY	EARTH BORROW	203.30	EST.			
										1	1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
										8	8		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
										8	8		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
										8	8		HR	TRUCK RENTAL	608.37	EST.			
										8	8		HR	LOADER RENTAL, TYPE I	608.40	EST.			
										2000	2000		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-			
										20	20		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
										1850	1850		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
										24	24		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
										275	275		HR	FLAGGERS	630.15	EST.			
										1	1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
										1	1		LS	TRAFFIC CONTROL	641.10	-			
										66650	66650		LF	4 INCH WHITE LINE	646.20	16.4			
										175	175		LF	4 INCH YELLOW LINE	646.21	-			
										55	55		LF	24 INCH STOP BAR	646.26	-			
										20	20		EACH	LETTER OR SYMBOL	646.30	-			
										50	50		LB	SEED	651.15	EST.			
										50	50		LB	FERTILIZER	651.18	EST.			
										1	1		TON	AGRICULTURAL LIMESTONE	651.20	EST.			
										2.5	2.5		TON	HAY MULCH	651.25	EST.			
										25	25		CY	TOPSOIL	651.35	EST.			
										500	500		SY	TEMPORARY EROSION MATTING	653.20	EST.			
										679	679		SF	TRAFFIC SIGNS, TYPE A	675.20	0.93			
										1785	1785		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-			
										68	68		EACH	REMOVING SIGNS	675.50	-			
										1	1		EACH	ERECTING SALVAGED SIGNS	675.60	EST.			
										59	59		EACH	SPECIAL PROVISION (DELINEATOR WITH STEEL POST)	900.620	-			
										850.25	850.25		LF	STEEL BEAM GUARDRAIL GALVANIZED, W/8 FT POST	621.205				
										2	2		EA	SUPPLEMENT AGREEMENT (STEEL BEAM GUARDRAIL GALVANIZED) (W/ W8x24x4'6" BRIDGE POST)	900.520				

PROJECT NAME: STATEWIDE NORTHEAST REGION
 PROJECT NUMBER: STP HRRR(8)
 FILE NAME: d:\0k316_wrk.dgn
 PROJECT LEADER: JLS
 DESIGNED BY: NLA
 QUANTITY SHEET
 PLOT DATE: 09-AUG-2011
 DRAWN BY: ITS
 CHECKED BY: JLS
 SHEET 4 OF 28