STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - BARTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.730, RT	A	TOWN SIGN	30	12		END 30 MPH						X		X											REMOVE EXISTING SIGN AND POST 422 FT SOUTH OF POLE #29			
		A	R2-1	24	30		SPEED LIMIT 50	5.00								1		X								INSTALL NEW SIGN AND POST AT TOWN LINE	X		
SB	MM 0.730, LT	F	R2-1	24	30		SPEED LIMIT 30	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST AT THE TOWN LINE AND ACROSS FROM THE R2-1 SIGN	X		
SB	MM 0.790, LT	F	W3-5	36	36		SPEED LIMIT 30	9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 422 FT SOUTH AND ACROSS FROM POLE #29	X		
		F	TOWN SIGN	24	30		REDUCE SPEED 30 MPH						X		X											REMOVE EXISTING SIGN AND POST 106 FT SOUTH AND ACROSS FROM POLE #29			
NB	MM 0.794, RT	A	W1-2R	30	30								X		X											REMOVE EXISTING SIGN AND POST 85 FT SOUTH OF POLE #29			
		A	W13-1P	18	18		40 M.P.H.						X													REMOVE EXISTING PLAQUE BELOW W1-2R SIGN ON THE SAME POST			
SB	MM 0.820, LT	F	VW-054	30	30		HIDDEN DRIVE RIGHT	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST 53 FT NORTH AND ACROSS FROM POLE #29		7	
SB	MM 0.840, LT	F	R2-5A	24	30		REDUCED SPEED AHEAD						X		X											REMOVE EXISTING SIGN AND POST 211 FT SOUTH AND ACROSS FROM POLE #31			
		F	TOWN SIGN	24	30		NEIGHBORHOOD WATCH						X													REMOVE EXISTING PLAQUE BELOW R2-5A SIGN			
NB	MM 0.880, RT	A	W1-2R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST DIRECTLY NEXT TO POLE #31	X		
		A	W13-1P	18	18		40 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-2R SIGN ON THE SAME POST	X		
SB	MM 0.920, LT TO MM 1.048, LT	F E		6	8		(16) TYPE II - 6" X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (16) BACK-TO-BACK 70 FT APART ON 8 POSTS, INSTALL FIRST 211 FT NORTH AND ACROSS FROM POLE #31		6	
SB	MM 1.060, LT	F	W1-2L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 50 FT NORTH OF POLE# 37	X		
		F	W13-1P	18	18		40 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-2L SIGN ON THE SAME POST	X		
										EA	EA	EA	EA 8	EA	EA 6		FT	FT 105	FT					LB	LB	LB	LB				
							SHEET SUBTOTALS	SF 42.25	SF	EA 8				EA 6		EA 7	FT 105			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(8)

FILE NAME: d10k316_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARTON TRAFFIC SIGN SUMMARY 1

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 9 OF 28