STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4 - PLAINFIELD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							MILL STREET																						
SB	MM 0.010, LT	F	R2-1	24	30		SPEED LIMIT 30						X		X											REMOVE EXISTING SIGN AND POST			
SB	MM 0.050, LT	H	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST AT SOUTHEAST CORNER OF RECREATION FIELD ROAD	X		
SB	MM 0.116, LT	F	R2-1	24	30		SPEED LIMIT 25	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 230 FT SOUTH OF MAIN STREET INTERSECTION	X		
NB	MM 0.150, RT	A	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST AT NORTHEAST END OF MILL STREET AND MAIN STREET INTERSECTION	X		
							FLOOD ROAD																						
NB	MM 0.015, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 80 FT WEST OF MIDDLE ROAD INTERSECTION	X		
SB	MM 0.060, LT	F	W3-1	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 300 FT SOUTHWEST OF MIDDLE ROAD INTERSECTION	X		
							GONYEAU ROAD																						
NB	MM 0.015, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST 75 FT EAST OF MIDDLE ROAD INTERSECTION	X		
SB	MM 0.090, LT	F	W3-1	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 480 FT EAST OF MIDDLE ROAD INTERSECTION	X		
							CENTER SCHOOL ROAD																						
NB	MM 0.015, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 75 FT SOUTHEAST OF MIDDLE ROAD INTERSECTION	X		
SB	MM 0.090, LT	F	W3-1	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 400 FT NORTHEAST OF MIDDLE ROAD INTERSECTION	X		
							BROOK ROAD																						
SB	MM 0.010, LT	F	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST 50 FT NORTHEAST OF MIDDLE ROAD INTERSECTION	X		
										EA	EA	EA	EA 7	EA	EA 7		FT	FT 150	FT		LB	LB	LB	LB				
							SHEET SUBTOTALS	SF 57.50	SF	EA 7				EA 7		EA 10	FT 150			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(8)

FILE NAME: d10k316_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLAINFIELD TRAFFIC SIGN SUMMARY 4

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 19 OF 28