STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - WALDEN

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							NOYESTAR ROAD																						
NB	MM 0.120, RT	A	W1-2MbR	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS ACROSS FROM POLE #WE/L33/LR		8	
		A	W16-8P	42	8		Cahoon Farm Rd	2.33																		INSTALL NEW PLAQUE BELOW W1-2MbR SIGN ON THE SAME POSTS		8	
SB	MM 0.209, LT	G	W1-7	48	24			8.00								2		X								INSTALL NEW SIGN ON 2 POSTS 50 FT NORTH OF POLE #WE/45/L37	X		
NB	MM 0.256 RT TO MM 0.330 RT	A B		6	8		(14) TYPE II - 6" X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (14) BACK-TO-BACK 60 FT APART ON 7 POSTS, INSTALL FIRST ACROSS FROM POLE #38		6	
NB	MM 0.456 RT TO MM 0.520 RT	A B		6	8		(10) TYPE II - 6" X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (10) BACK-TO-BACK 60 FT APART ON 5 POSTS, INSTALL FIRST 185 FT SOUTH OF DRIVE WAY AND/OR 612 FT SOUTH OF POLE #3/1375		6	
NB	MM 0.803, RT	A	OM3-R	12	36			3.00								1		X								INSTALL NEW SIGN AND POST AT SOUTHEAST END OF BRIDGE CORNER	X		
SB	MM 0.803, LT	E	OM3-L	12	36			3.00								1		X								INSTALL NEW SIGN AND POST AT SOUTHWEST END OF BRIDGE CORNER	X		
NB	MM 0.823, RT	B	OM3-L	12	36			3.00								1		X								INSTALL NEW SIGN AND POST AT NORTHEAST END OF BRIDGE CORNER	X		
SB	MM 0.823, RT	F	OM3-R	12	36			3.00								1		X								INSTALL NEW SIGN AND POST AT NORTHWEST END OF BRIDGE CORNER	X		
NB	MM 0.935, LT	A	W1-2MbR	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 65 FT NORTH AND ACROSS FROM COLE ROAD		8	
		A	W16-8P	24	8		Rock Rd	1.33																		INSTALL NEW PLAQUE BELOW W1-2MbR SIGN ON THE SAME POSTS		8	
SB	MM 1.020, LT	F	W1-2L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 25 FT SOUTH OF POLE #3/141/1039	X		
NB	MM 1.033, RT	D	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST	X		
										EA	EA	EA	EA 1	EA	EA 1		FT	FT 180	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 54.16	SF	EA 1				EA 1		EA 12	FT 180			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(8)

FILE NAME: d10k316_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
WALDEN TRAFFIC SIGN SUMMARY 1

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 21 OF 28