STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - WALDEN

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHS = STANDARD HIGHWAY SIGN BOOK)	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
							CAHOON FARM ROAD																						
WB	MM 0.010, LT	F	RI-1	30	30		STOP	6.25					X		X	1		X								INSTALL NEW SIGN AND POST	X		
EB	MM 0.020, RT	A	SI-1	36	36	F-Y-G		9.00					X		X	2		X								INSTALL NEW SIGN ON 2 POSTS	X		
		A	S4-3P	36	12	F-Y-G	SCHOOL	3.00																		INSTALL NEW PLAQUE BELOW SI-1 SIGN ON THE SAME POSTS	X		
EB	MM 0.0490, RT	A	TOWN SIGN	18	18		SLOW SCHOOL ZONE						X		X											REMOVE EXISTING SIGN AND POST			
		A	R2-1	18	24		SPEED LIMIT 25						X													REMOVE EXISTING SIGN			
EB	MM 0.0490, RT	A	R2-1	24	30		SPEED LIMIT 25	5.00								1		X								INSTALL NEW SIGN AND POST 30 FT WEST AND ACROSS FROM POLE *WE/L37/RI	X		
WB	MM 0.0490, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST 30 FT +/- WEST OF POLE *ER/L37/RI	X		
WB	MM 0.0780, LT	F	W3-1	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 30 FT EAST AND ACROSS FROM CEMETERY DRIVE	X		
WB	MM 0.200, LT	F	SI-1	30	30								X		X											REMOVE EXISTING SIGN AND POST			
EB	MM 0.212, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST 20 FT WEST AND ACROSS FROM POLE *WE/L37/R4	X		
WB	MM 0.200 ~~0.212~~, LT	F	R2-1	18	24		SPEED LIMIT 25						X		X											REMOVE EXISTING SIGN AND POST			
WB	MM 0.212, LT	F	R2-1	24	30		SPEED LIMIT 25	5.00								1		X								INSTALL NEW SIGN AND POST 20 FT WEST OF POLE *WE/L37/4	X		
WB	MM 0.218, LT	F		18	18		SLOW SCHOOL ZONE → ◇						X		X											REMOVE EXISTING SIGN AND POST			
WB	MM 0.250, LT	F	SI-1	36	36	F-Y-G		9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 45 FT EAST AND ACROSS FROM POLE *WE/L-37/R5	X		
		F	S4-3P	36	12	F-Y-G	SCHOOL	3.00																		INSTALL NEW PLAQUE BELOW SI-1 SIGN ON THE SAME POSTS	X		
										EA	EA	EA	EA 5 ~~7~~	EA	EA ~~4~~ 6			FT 150										
							SHEET SUBTOTALS	SF 56.50	SF				EA ~~5~~ 7		EA ~~4~~ 6	EA 10		FT 150		EA		LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(8)

FILE NAME: dl0k316_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
WALDEN TRAFFIC SIGN SUMMARY 2

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 22 OF 28