STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - BARTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 1.110, LT	F	W1-2L	30	30								X		X											REMOVE EXISTING SIGN AND POST 285 FT NORTH OF POLE #37			
		F	W13-1P	18	18		40 M.P.H.						X													REMOVE EXISTING PLAQUE BELOW W1-2L SIGN ON THE SAME POST			
SB	MM 1.250, LT	F	W7-1	30	30			6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST 447 FT SOUTH AND ACROSS FROM POLE #43	X		
NB	MM 1.330, RT	A	W1-2L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 25 FT SOUTH OF POLE #43	X		
		A	W13-1P	18	18		40 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-2L SIGN ON THE SAME POST	X		
NB	MM 1.350, RT	D	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST FOR MAY POND ROAD	X		
SB	MM 1.460, LT	F	VW-054	30	30		HIDDEN DRIVE RIGHT	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST 475 FT SOUTH OF POLE #49-1		7	
SB	MM 1.560, LT	F	W1-2R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 50 FT NORTH OF POLE #49-1	X		
		F	W13-1P	18	18		40 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-2R SIGN ON THE SAME POST	X		
SB	MM 1.610, LT	F	W1-2R	30	30								X		X											REMOVE EXISTING SIGN AND POST 317 FT SOUTH OF POLE #59			
NB	MM 1.960, RT	A	TOWN SIGN	30	30		SLOW						X		X											REMOVE EXISTING SIGN AND POST 422 FT SOUTH AND ACROSS FROM POLE #59			
		A	OM1-1	18	18								X													REMOVE EXISTING SIGN BELOW SLOW SIGN			
NB	MM 2.050, RT	A	OM3-R	12	36								X		X											REMOVE EXISTING SIGN AND POST 53 FT NORTH AND ACROSS FROM POLE #59			
NB	MM 2.060, RT	A	W1-4R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 63 FT SOUTH AND ACROSS FROM POLE 3/7/60	X		
		A	W13-1P	18	18		35 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-4R SIGN ON SAME POST	X		
SB	MM 2.065, LT	F	OM3-R	12	36								X		X											REMOVE EXISTING SIGN AND POST 40 FT SOUTH OF POLE 3/7/60			
										EA	EA	EA	EA 10	EA	EA 8		FT	FT 90	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 44.25	SF	EA 10				EA 8		EA 6	FT 90			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(8)

FILE NAME: d10k316_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARTON TRAFFIC SIGN SUMMARY 2

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 10 OF 28