STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5 - BARTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) lb/ft 1.75 / 1.88	SQUARE STEEL (in) lb/ft 2.00 / 2.42	SQUARE STEEL (in) lb/ft 2.50 / 3.35	TUBULAR STEEL O/(in) lb/ft FOUNDATION	TUBULAR STEEL O/(in) lb/ft 3.00 / 7.60	TUBULAR STEEL O/(in) lb/ft 3.50 / 9.00	TUBULAR STEEL O/(in) lb/ft 4.00 / 10.80	TUBULAR STEEL O/(in) lb/ft 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 3.670, RT	A	WI-10R	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS NEXT TO POST #37/106	X		
		A	W13-1P	18	18		40 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW WI-10R SIGN ON RIGHT HAND POST FARTHEST FROM TRAFFIC	X		
SB	MM 3.760, LT	H	RI-1	30	30		STOP			X				X												RETAIN EXISTING SIGN AND POST 475 FT NORTH AND ACROSS FROM POLE #37/106			
NB	MM 3.780, RT	A	M3-2	24	12		EAST	2.00								1		X								INSTALL NEW SIGN AND POST NEXT TO POLE #34 SIGN COLORS ARE GREEN AND WHITE	X		
		A	MI-6	24	24		VERMONT 16	4.00					X		X											INSTALL NEW SIGN BELOW M3-2 SIGN ON THE SAME POST			E136B
SB	MM 3.810, LT	F	WI-10L	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 158 FT NORTH AND ACROSS FROM POLE #34	X		
		F	W13-1P	18	18		40 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW WI-10L SIGN ON LEFT HAND POST FARTHEST FROM TRAFFIC	X		
NB	MM 3.980, RT	A	VW-202	24	24		TRUCKS ENTERING						X		X											REMOVE EXISTING SIGN AND POST 1056 FT NORTH OF POLE #34			
		A	VW-081	30	30		TRUCKS ENTERING RIGHT	6.25								1		X								INSTALL NEW SIGN AND POST 1056 FT NORTH OF POLE #34		7	
NB	MM 4.080, RT	D	RI-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST 875 FT SOUTH OF POLE #18	X		
SB	MM 4.180, LT	F	VW-202	24	24		TRUCKS ENTERING						X		X											REMOVE EXISTING SIGN AND POST 347 FT SOUTH AND ACROSS FROM POLE #18			
		F	VW-084	30	30		TRUCKS ENTERING LEFT	6.25								1		X								INSTALL NEW SIGN AND POST 1056 FT NORTH OF POLE #18		7	
NB	MM 4.240, RT	A	WI-4R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST NEXT TO POLE #B/11/5/32	X		
SB	MM 4.290, LT	H	RI-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST AT THE CORNER OF FISKE ROAD AND WILLOUGHBY LAKE ROAD INTERSECTION	X		
SB	MM 4.450, LT	F	WI-4R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST DIRECTLY NEXT TO POLE #B/11/5/32	X		
NB	MM 4.470, RT TO MM 4.481, RT	A B		6	8		(8) TYPE II - 6" X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (8) BACK-TO-BACK 20 FT APART ON 4 POSTS, INSTALL FIRST 52 FT SOUTH AND ACROSS POLE #133		6	
										EA 1	EA	EA	EA ~~4~~ 5	EA 1	EA ~~4~~ 5													
																	FT	FT 165	FT											
																					LB	LB	LB	LB					
			SHEET SUBTOTALS					SF 66.00	SF				EA ~~5~~ 6		EA ~~5~~ 6	EA 11		FT 165		EA										

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(8)

FILE NAME: d10k316_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BARTON TRAFFIC SIGN SUMMARY 5

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 13 OF 28