STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - PLAINFIELD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHS = STANDARD HIGHWAY SIGN BOOK)	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
SB	MM 0.000, LT	G	VD-024	72	10		Barre Town / Plainfield	5.00								2		X								INSTALL NEW SIGN ON 2 POSTS ACROSS FROM POLE *GMP/13/50/T2 1/2		7	
SB	MM 0.000, LT	F	R2-1	24	30		SPEED LIMIT 40	5.00								1		X								INSTALL NEW SIGN AND POST 5 FT SOUTH AND ACROSS FROM POLE *GMP/132/T2 1/2	X		
NB	MM 0.000, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST ADJACENT TO POLE *GMP/13/50/T2 1/2	X		
NB	MM 0.030, RT	A	W2-2L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 40 FT SOUTH OF POLE *GMPC/1	X		
		A	W16-8P	24	8		Flood Rd	1.33																		INSTALL NEW PLAQUE BELOW W2-2L SIGN ON THE SAME POST		7	
SB	MM 0.051, LT	F	R2-1	24	30		SPEED LIMIT 35	~~5.00~~					X		X	~~1~~		~~X~~								REPLACE EXISTING SIGN AND POST 70 FT NORTH AND ACROSS FROM POLE *GMPC/1	X		
SB	MM 0.068, LT	H	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST 37 FT SOUTH AND ACROSS FROM POLE *GMP/2	X		
NB	MM 0.075, RT	C	W1-7	48	24			8.00								2		X								INSTALL NEW SIGN ON 2 POSTS ADJACENT TO POLE *GMP/2	X		
NB	MM 0.090, RT	B	R1-1	30	30		STOP	6.25								1		X								INSTALL NEW SIGN AND POST 80 FT NORTH OF POLE* GMP/2	X		
SB	MM 0.090, ~~RT~~ LT	F	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST 80 FT NORTH AND ACROSS FROM POLE *GMP/2	X		
		F	W4-4bP	24	12		ONCOMING TRAFFIC DOES NOT STOP	2.00																		INSTALL NEW PLAQUE BELOW R1-1 SIGN ON THE SAME POST	X		
NB	MM 0.110, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 340 FT SOUTH OF POLE *GMP/4/76/NET	X		
SB	MM 0.160, LT	F	W3-1	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 65 FT SOUTH AND ACROSS FROM POLE *GMP/4/76/NET	X		
SB	MM 0.190, LT	F	W3-1	30	30		STOP AHEAD						X		X											REMOVE EXISTING SIGN AND POST			
NB	MM 0.550, RT	A	W2-2R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST ACROSS FROM POLE *83	X		
		A	W16-8P	30	8		Gonyeau Rd	1.67																		INSTALL NEW PLAQUE BELOW W2-2R SIGN ON THE SAME POST		7	
										EA	EA	EA	EA 6	EA	EA 6			FT 210					LB	LB	LB	LB					
SHEET SUBTOTALS								SF ~~75.50~~ 70.50	SF				EA 6		EA 6	EA ~~14~~ 13		FT 210		EA			LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(8)

FILE NAME: d10k316_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLAINFIELD TRAFFIC SIGN SUMMARY 1

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 16 OF 28