STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 - PLAINFIELD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 2.750, RT	D	RI-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST AT NORTH END OF CENTER SCHOOL ROAD	X		
NB	MM 2.765, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 135 FT NORTH OF CENTER SCHOOL ROAD	X		
NB	MM ~~2.850,~~ 2.950 RT	A	VW-054	30	30		HIDDEN DRIVE RIGHT						X		X											REMOVE EXISTING SIGN AND POST			
NB	MM 3.264, RT	A	W2-3R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 75 FT NORTH AND ACROSS FROM POLE #GMP/2	X		
		A	W16-8P	24	8		Lower Rd	1.33																		INSTALL NEW PLAQUE BELOW W2-3R SIGN ON THE SAME POST		7	
SB	MM 3.310, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 320 FT NORTH OF POLE #GMP/2	X		
							BARRE HILL ROAD																						
NB	MM 0.010, RT	A	R2-1	24	30		SPEED LIMIT 30	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 25 FT SOUTH AND ACROSS FROM POLE #GMP/21/14	X		
NB	MM 0.030, RT	A	W7-1	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 80 FT NORTH AND ACROSS FROM POLE #GMP/21/14	X		
SB	MM 0.050, RT	F	W2-3R	30	30			6.25								2		X								INSTALL NEW SIGN ON 2 POSTS 25 FT NORTH OF POLE #GMP/20/13/NET	X		
		F	W16-8aP	48	15		MIDDLE RD LOWER RD	5.00																		INSTALL NEW PLAQUE BELOW W2-3R SIGN ON THE SAME POSTS		7	
NB	MM 0.350, RT	A	R2-5A	24	30		REDUCED SPEED AHEAD						X		X											REMOVE EXISTING SIGN AND POST			
NB	MM 0.390, RT	A	W3-5	36	36		SPEED LIMIT 25	9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 170 FT NORTH AND ACROSS FROM POLE #GMP/11/4/NET	X		
NB	MM 0.445, RT	A	R2-1	24	30		SPEED LIMIT 25	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 435 FT NORTH AND ACROSS FROM POLE #GMP/11/4/NET	X		
SB	MM 0.476, LT	F	R2-1	24	30		SPEED LIMIT 30	5.00								1		X								INSTALL NEW SIGN AND POST 100 FT SOUTH OF POLE #GMP/25K	X		
										EA	EA	EA	EA 7	EA	EA 7		FT	FT 180	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 65.33	SF				EA 7		EA 7	EA 12		FT 180		EA		LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(8)

FILE NAME: d10k316_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLAINFIELD TRAFFIC SIGN SUMMARY 3

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 18 OF 28