

TRAFFIC SIGN SUMMARY SHEET 1 - BERKSHIRE

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL O/(in)				SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL								
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		FOUNDATION			lb/ft						DETAIL IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER						
																	1.75	2.00	2.50	3.00	3.50	4.00	5.00											
NB	MM, 0.070, RT	A	R2-1	24	30					X				X										RETAIN EXISTING SIGN AND POST 370 FT NORTH FROM POLE #39C/12										
SB	MM, 0.513, LT	F	R2-1	24	30					X				X										RETAIN EXISTING SIGN AND POST ACROSS FROM POLE #39C/4										
NB	MM, 0.520, RT	A	SI-1	36	36	F-Y-G		9.00					X	X	2		X							REPLACE EXISTING SIGN ON 2 POSTS 95 FT NORTH FROM POLE #39C/4	X									
		A	S4-3P	36	12	F-Y-G		3.00																INSTALL NEW PLAQUE BELOW SI-1 SIGN ON THE SAME POSTS	X									
NB	MM, 0.536, RT	A	W2-1	30	30								X	X										REMOVE EXISTING SIGN AND POST NEXT TO POLE #39C/3										
SB	MM, 0.594, LT	F	M3-3	24	12			2.00					X	X	1		X							REPLACE EXISTING SIGN AND POST 74 FT SOUTH OF AND ACROSS FROM POLE #39C/2	X									
		F	MI-4	30	24								X											REMOVE EXISTING US-118 ROUTE SIGN BELOW M3-3 SIGN ON THE SAME POST										
		F	MI-6	30	24			5.00																INSTALL NEW SIGN BELOW M3-3 SIGN ON THE SAME POST 74 FT SOUTH OF AND ACROSS FROM POLE #39C/2	X									
SB	MM, 0.604, LT	G	R5-1	30	30			6.25					X	X	1		X							REPLACE EXISTING SIGN AND POST 16 FT SOUTH OF AND ACROSS FROM POLE #39C/2 ON SOUTH SIDE OF SCHOOL DRIVE	X									
SB	MM, 0.604, LT	H	RI-1	30	30			6.25					X		1		X							REPLACE EXISTING SIGN AND INSTALL NEW SIGN AND POST 3 FT WEST OF DO NOT ENTER SIGN AND POST FACING TRAFFIC EXISTING SCHOOL DRIVE	X									
SB	MM, 0.612, LT	G	R5-1	30	30			6.25					X	X	1		X							REPLACE EXISTING SIGN AND POST 26 FT NORTH OF AND ACROSS FROM POLE #39C/2 ON NORTH SIDE OF SCHOOL DRIVE	X									
SB	MM, 0.612, LT	H	RI-1	30	30			6.25					X		1		X							REPLACE EXISTING SIGN AND INSTALL NEW SIGN AND POST 3 FT WEST OF DO NOT ENTER SIGN AND POST FACING TRAFFIC EXITING SCHOOL DRIVE	X									
NB	MM, 0.620, RT	A	W2-1	36	36			9.00							2		X							INSTALL NEW SIGN ON 2 POSTS 69 FT NORTH OF POLE #39C/ 2	X									
		A	W16-8aP	48	15			5.00																INSTALL NEW STREET NAME PLAQUE BELOW THE NEW W2-1 SIGN ON THE SAME POSTS			8							
NB	MM, 0.659, RT	C	VR-017	24	30								X											RETAIN SIGN AND POST NEXT TO POLE #39C/1										
<p>FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".</p>																																		
SHEET SUBTOTALS								SF	SF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA		
								58.00		3	8	3	5					135																

PROJECT NAME: STATEWIDE NORTHWEST REGION
 PROJECT NUMBER: STP HRRR(9)
 FILE NAME: dl0k318_wrk.dgn
 PROJECT LEADER: JLS
 DESIGNED BY: NLA
 BERKSHIRE TRAFFIC SIGN SUMMARY 1

PLOT DATE: 22-OCT-2012
 DRAWN BY: ITS
 CHECKED BY: JLS
 SHEET 10 OF 54