STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - BERKSHIRE

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM, 0.663, LT	H	RI-1	30	30		STOP			X				X												RETAIN EXISTING SIGN AND POST ACROSS FROM POLE #39C/1			
NB	MM, 0.668, RT	D	RI-1	30	30		STOP			X				X												RETAIN EXISTING SIGN AND POST NEXT TO POLE #39C/1BS ON NORTH SIDE OF RICHFORD ROAD			
SB	MM, 0.671, LT	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST ACROSS FROM POLE #39C/1BS ON THE NORTH SIDE OF WATER TOWER RD		6	
SB	MM, 0.714, LT	F	S1-1	36	36	F-Y-G		9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 250 FT NORTH OF AND ACROSS FROM POLE #39C/1BS	X		
		F	S4-3P	36	12	F-Y-G	SCHOOL	3.00																		INSTALL NEW PLAQUE BELOW S1-1 SIGN ON THE SAME POSTS	X		
NB	MM, 0.724, RT	A	M3-1	24	12		NORTH	2.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 302 FT NORTH OF POLE #39C/1BS	X		
		A	M1-4	30	24		118	5.00					X													REPLACE EXISTING SIGN BELOW M3-1 SIGN ON THE SAME POST	X		
SB	MM, 0.752, LT		W2-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 53 FT SOUTH OF POLE #BT/7C	X		
		F	W16-8aP	48	15		← Watertower Rd Richford Rd →	5.00																		INSTALL NEW PLAQUE BELOW W2-1 SIGN ON THE SAME POSTS		8	
NB	MM, 0.754, RT	A	R2-1	24	30		SPEED LIMIT 50			X				X												RETAIN EXISTING SIGN AND POST 42 FT SOUTH OF AND ACROSS FROM POLE #BT/7C			
SB	MM, 0.762, LT	F	S1-1	36	36								X		X											REMOVE EXISTING SIGN AND POST NEXT TO POLE #BT/7C			
SB	MM, 0.800, LT	F	W2-1	36	36								X		X											REMOVE EXISTING SIGN AND POSTS 200 FT NORTH OF POLE #BT/7C			
NB	MM, 1.130, RT	A	W2-1	36	36								X		X											REMOVE EXISTING SIGN AND POSTS 454 FT SOUTH OF POLE #BT/196/29/1			
NB	MM, 1.175, RT	A	W2-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 216 FT SOUTH OF POLE #BT/196/29/1	X		
NB	MM, 1.200, RT	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST NEXT TO POLE #BT/196/29/1 AND ON THE SOUTH OF NORTH RD	X	6	
SB	MM, 1.200, LT	H	RI-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST 85 FT SOUTH OF AND ACROSS FROM POLE #BT/196/29/1	X		
										EA 3	EA	EA	EA 8	EA 3	EA 7		FT	FT 150	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 58.25	SF	EA 11				EA 10		EA 10	FT 150			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: dl0k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BERKSHIRE TRAFFIC SIGN SUMMARY 2

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 11 OF 54