STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 - BERKSHIRE

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O (in) FOUNDATION	TUBULAR STEEL O (in) 3.00 lb/ft 7.60	TUBULAR STEEL O (in) 3.50 lb/ft 9.00	TUBULAR STEEL O (in) 4.00 lb/ft 10.80	TUBULAR STEEL O (in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL IN SHS	SIGN DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM, 1.211, LT	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 26 FT SOUTH OF AND ACROSS FROM POLE *BT/196/29/1		6	
NB	MM, 1.216, RT	D	RI-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST NEXT TO POLE *BT/196/29/1 AND NORTH OF NORTH RD	X		
SB	MM, 1.280, LT	F	W2-1	36	36			9.00					X		X	2		X								REPLACE EXISTING SIGN ON 2 POSTS ACROSS FROM POLE *BT/195/2	X		
NB	MM, 1.814, RT	A	W1-4R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST NEXT TO POLE *BT/186/11	X		
		A	W13-1P	18	18		40 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-4R SIGN ON THE SAME POST	X		
SB	MM, 1.850, LT	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						X		X											REMOVE EXISTING SIGN AND POST 190 FT NORTH OF AND ACROSS FROM POLE *BT/186/11			
SB	MM, 1.850, LT	F	S3-1	36	36	F-Y-G		9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 190 FT NORTH AND ACROSS FROM POLE *BT/186/11	X		
SB	MM, 1.920, LT	F	W1-6L	48	24			8.00								2		X								INSTALL NEW SIGN ON 2 POSTS ADJACENT TO POLE *29	X		
SB	MM, 1.920, LT	E	W1-6R	48	24			8.00								2		X								INSTALL NEW SIGN ON 2 POSTS ADJACENT TO POLE *29	X		
SB	MM, 2.090, LT	F	W1-4R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 898 FT NORTH OF POLE *29	X		
		F	W13-1P	18	18		40 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-4R SIGN ON THE SAME POST	X		
NB	MM, 2.250, RT	A	OM-3R	12	36			3.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 475 FT SOUTH OF POLE*BT/177	X		
SB	MM, 2.250, LT	E	OM-3L	12	36			3.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 475 FT SOUTH OF AND ACROSS FROM POLE *BT/177	X		
NB	MM, 2.269, RT	B	OM-3L	12	36			3.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 375 FT SOUTH OF POLE *BT/177	X		
SB	MM, 2.269, LT	F	OM-3R	12	36			3.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 375 FT SOUTH OF AND ACROSS FROM POLE *BT/177	X		
NB	MM, 2.340, RT	A	W1-2L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST RIGHT NEXT TO POLE *BT/177	X		
										EA	EA	EA	EA 8	EA	EA 8		FT	FT 255	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 80.50	SF	EA 8				EA 8		EA 17	FT 255			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: dl0k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BERKSHIRE TRAFFIC SIGN SUMMARY 3

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 12 OF 54