STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4 - BERKSHIRE

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O (in) FOUNDATION	TUBULAR STEEL O (in) 3.00 lb/ft 7.60	TUBULAR STEEL O (in) 3.50 lb/ft 9.00	TUBULAR STEEL O (in) 4.00 lb/ft 10.80	TUBULAR STEEL O (in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM, 2.466, LT	F	WI-2R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST RIGHT ACROSS FROM POLE #39/13/14/20	X		
NB	MM, 2.670, RT	A	WI-2R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST RIGHT NEXT TO POLE #14/15	X		
		A	WI3-IP	18	18			2.25																		INSTALL NEW PLAQUE BELOW WI-2R SIGN ON THE SAME POST	X		
SB	MM, 2.724, LT	F	WI-6L	48	24			8.00								2		X								INSTALL NEW SIGN ON 2 POSTS 85 FT SOUTH OF POLE #39/8/14/13	X		
SB	MM, 2.724, LT	E	WI-6R	48	24			8.00								2		X								INSTALL NEW SIGN ON 2 POSTS 85 FT SOUTH OF POLE #39/8/14/13	X		
SB	MM, 2.740, LT	F	WI-6L	48	24								X		X											REMOVE EXISTING SIGN ON 2 POSTS NEXT TO POLE #39/8/14/13 BACK-TO-BACK WITH WI-6R			
SB	MM, 2.740, LT	E	WI-6R	48	24								X		X											REMOVE EXISTING SIGN ON 2 POSTS NEXT TO POLE #39/8/14/13 AND BACK-TO-BACK WITH WI-6L			
SB	MM, 2.780, LT	F	WI-2L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 200 FT SOUTH OF POLE #39/7	X		
		F	WI3-IP	18	18			2.25																		INSTALL NEW PLAQUE BELOW WI-2L SIGN ON THE SAME POST	X		
SB	MM, 2.820, LT	F	WI-IL	30	30								X		X											REMOVE EXISTING SIGN ON 2 POSTS NEXT TO POLE #39/7			
NB	MM, 2.830, RT	A	R2-5	24	30								X		X											REMOVE EXISTING SIGN AND POST 53 FT NORTH OF AND ACROSS FROM POLE #39/7			
NB	MM, 2.830, RT	A	W3-5	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS AT THE R2-5A SIGN LOCATION	X		
							RICHFORD ROAD																						
SB	MM, 0.000, LT	F	RI-1	30	30					X				X												RETAIN EXISTING SIGN AND POST 116 FT SOUTH OF POLE #9A			
NB	MM, 0.000, RT	A	RI-1	30	30					X				X												RETAIN EXISTING SIGN AND POST 116 FT SOUTH OF AND ACROSS FROM POLE #9A AND BACK-TO-BACK WITH VR-017 SIGN			
		B	VR-017	24	30					X																RETAIN EXISTING SIGN AND POST 116 FT SOUTH OF AND ACROSS FROM POLE #9A AND BACK-TO-BACK WITH RI-1 SIGN			
										EA 3	EA	EA	EA 4	EA 2	EA 4		FT	FT 135	FT					LB	LB	LB	LB				
							SHEET SUBTOTALS	SF 48.25	SF	EA 7				EA 6		EA 9	FT 135			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: dl0k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BERKSHIRE TRAFFIC SIGN SUMMARY 4

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 13 OF 54