STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - CHARLOTTE

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
EB	MM, 0.426, RT	A	R2-1	24	30		SPEED LIMIT 30	5.00								1		X								INSTALL NEW SIGN AND POST 15 FT NORTH FROM POLE #GMP/72/CTC/47	X		
EB	MM, 0.493, RT	A	W3-1	36	36			9.00					X		X	2		X								REPLACE EXISTING SIGN ON 2 POSTS 130 FT SOUTH FROM POLE #GMP/75/CTC/2/50	X		
WB	MM, 0.493, LT	F	S1-1	36	36	F-Y-G		9.00					X		X	2		X								REPLACE EXISTING SIGN ON 2 POSTS 130 FT SOUTH AND ACROSS FROM POLE #GMP/75/CTC/2/50	X		
		F	W16-9P	24	12	F-Y-G	AHEAD						X													REMOVE EXISTING PLAQUE BELOW S1-1			
			S4-3P	36	12	F-Y-G	SCHOOL	3.00																		INSTALL NEW PLAQUE BELOW THE REPLACED S1-1 SIGN ON THE SAME 2 POSTS	X		
WB	MM, 0.500, LT	F	R2-1	24	30		SPEED LIMIT 30						X		X											REMOVE EXISTING SIGN AND POST 95 FT SOUTH FROM POLE #GMP/75/CTC/2/50			
WB	MM, 0.530, LT	F	R2-1	24	30		SPEED LIMIT 30	5.00								1		X								INSTALL NEW SIGN AND POST 64 FT NORTH AND ACROSS FROM POLE #GMP/75/CTC/2/50.	X		
EB	MM, 0.540, RT	A	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST 117 FT NORTH FROM POLE #GMP/75/CTC/2/50	X		
		A	R1-3	12	6		4-WAY						X													REMOVE EXISTING PLAQUE BELOW R1-1 SIGN ON THE SAME POST			
		A	R1-3P	18	6		ALL WAY	0.75																		INSTALL NEW PLAQUE BELOW THE REPLACED R1-1 SIGN ON THE SAME POST	X		
WB	MM, 0.540, LT	H	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST 117 FT NORTH AND ACROSS FROM POLE #GMP/75/CTC/2/50	X		
		H	R1-3	18	6		4-WAY						X													REMOVE EXISTING PLAQUE BELOW R1-1 SIGN 117 FT NORTH AND ACROSS FROM POLE #GMP/75/CTC/2/50			
		H	R1-3P	12	6		ALL WAY	0.75																		INSTALL NEW PLAQUE BELOW THE REPLACED R1-1 SIGN ON THE SAME POST	X		
EB	MM, 0.540, RT +50 FT, RT	C	R2-1	24	30		SPEED LIMIT 45	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 117 FT NORTH FROM POLE #GMP/75/CTC/2/50 ON MT. PHILO ROAD	X		
WB	MM, 0.540, LT +350 FT, LT	H	W3-1	36	36			9.00					X		X	2		X								REPLACE EXISTING SIGN AND INSTALL NEW SIGN ON 2 POSTS 117 FT NORTH AND ACROSS FROM POLE #GMP/75/CTC/2/50	X		
										EA	EA	EA	EA 10	EA	EA 7		FT	FT 165	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 59.00	SF	EA 10				EA 7		EA 11	FT 165			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: dl0k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
CHARLOTTE TRAFFIC SIGN SUMMARY 2

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 22 OF 54